

LOCATION			GUARDRAIL														REMARKS	
MM	MM	POS	203.30	621.20	621.50	621.51	621.60	621.76	621.77	621.79	621.80	651.35	653.20	676.10	676.12	676.15		900.640
			EARTH BORROW CY	STEEL BEAM GUARDRAIL GALV. LF	MANUFACT. TERMINAL SECTION, FLARED EACH	MANUFACT. TERMINAL SECTION, TANGENT EACH	ANCHOR FOR STEEL BEAM RAIL EACH	REPLACE GUARDRAIL POST ASSEMBLY EACH	REPLACE GUARDRAIL BEAM ASSEMBLY EACH	ADJUST HEIGHT OF GUARDRAIL LF	REMOVAL AND DISPOSAL OF GUARDRAIL LF	TOPSOIL CY	TEMP. EROSION MATTING SY	DELIN. W/STEEL POST EACH	REMOVAL OF EXIST. DELIN. EACH	REMOVE AND REPLACE REFLECTOR UNIT EACH		S.P. (ALUMINUM APPROACH RAILING) LF
MIDDLESEX SB																		
59.250	58.809	RT				← MTS RETAINED		6	2	575.00	50.00			2	2	93		
58.848	58.715	RT		50.00				1	5		50.00			2	2	28		
58.809	58.715	LT		25.00							25.00			2	2	20		
58.690	58.675	RT												2	2	3		
58.690	58.615	LT		112.50							112.50			2	2	16		
58.675	58.356	RT		67.50				4	2		67.50			2	2	67		
58.257	58.067	RT		18.75				3	7		18.75			2	2	40		
58.012	57.320	RT		100.00				10	10	50.00	100.00			2	2	146		
56.966	<del>55.592</del>	RT		200.00				3	3		200.00			2	2	303		
56.373	56.199	LT		62.50							62.50			2	2	37		
55.661	55.437	LT		37.50							37.50			2	2	47		
<del>55.472</del>	55.278	RT		1,070.00				1			1,070.00			2	2			
55.353	55.113	LT		62.50						100.00	62.50			2	2	51		
55.028	54.830	RT		112.50							112.50			2	2	42		
54.909	54.830	LT		100.00							100.00			2	2	17		
57.780	54.770	LT												2	2	636		
54.770	54.759	RT												2	2	2		
54.347	54.051	LTRT												2	2	63		
MONTPELIER SB																		
54.051	53.527	RT		287.50							287.50			2	2	111		
53.869	53.521	LT		37.50							37.50			2	2	73		
53.340	52.982	RT		125.00							125.00			2	2	76		
53.335	53.324	LT												2	2	2		
52.982	52.925	LT												2	2	12		
52.961	52.925	RT												2	2	8		
52.894	52.871	LT												2	2	5		
52.894	52.871	RT		12.50							12.50			2	2	5		
52.689	52.630	RT												2	2	12		
52.662	52.585	LT												2	2	16		
SUBTOTAL SHEET 10			500.0	11,673.75	1 10	← 4	4	78	71	6,650.00	12,173.75	100.0	80.0	102	102	1,604	25.00	
SUBTOTAL SHEET 11			0.0	2,518.75	← 1	← 0	← 2	27	78	725.00	2,518.75	0.0	0.0	56	56	1,931	0.00	
PROJECT SUBTOTAL			500.0	14,192.50	←	← 4	← 5	105	149	7,375.00	14,692.50	100.0	80.0	158	158	3,535	25.00	
TOTAL ROUNDING			EST	-	-	-	-	-	-	-	-	EST	EST	-	-	EST	-	
PROJECT TOTAL			500.0	14,192.50	← 11	← 4	← 6	105	149	7,375.00	14,692.50	100.0	80.0	158	158	3,535	25.00	

PROJECT NAME: MONTPELIER-WATERBURY  
 PROJECT NUMBER: IM SURF(59)  
 FILE NAME: pl6v098 Montpelier-Water.dgn PLOT DATE: 20-MAR-2018  
 PROJECT LEADER: M. BOGACZYK DRAWN BY: N. PAPPAS  
 DESIGNED BY: N. PAPPAS CHECKED BY: M. BOGACZYK  
 ITEM DETAIL SHEET 2 SHEET 12 OF 34