

# QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
	ROADWAY	ROADWAY (NO FEDERAL PARTICIPATIO	ROADWAY (NO FEDERAL/STAT E	BRIDGE	FULL C.E. ITEMS	ROADWAY (ALTERNATE A)	ROADWAY (ALTERNATE B)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS		
											END OPTION FF							
											BEGIN OPTION GG							
	68							68		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-	100	LB	DITCH CLEANING		
	68							68		EACH	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493	-	4	LB	SLOPE EROSION PREVENTION		
	68							68		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-	230	LB	TURF ESTABLISHMENT		
														6	LB	ROUNDING		
														340	LB	TOTAL		
											END OPTION GG							
	190200							190200		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	1864	5046	SY	DITCH CLEANING		
	154500							154500		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	1430	111	SY	SLOPE EROSION PREVENTION		
	780							780		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	8	475	SY	GUARDRAIL END SECTIONS		
	136							136		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-	68	SY	ROUNDING		
	17300							17300		EACH	LINE STRIPING TARGETS	646.76	162	5700	SY	TOTAL		
	340							340		LB	SEED	651.15	6					
	1280							1280		LB	FERTILIZER	651.18	EST					
	5							5		TON	AGRICULTURAL LIMESTONE	651.20	EST					
	8							8		TON	HAY MULCH	651.25	EST					
	180							180		CY	TOPSOIL	651.35	EST					
	115							115		SY	GRUBBING MATERIAL (6")	651.40	4					
	5700							5700		SY	TEMPORARY EROSION MATTING	653.20	68					
	110							110		LF	EROSION LOG	653.60	10					
	601							601		SF	TRAFFIC SIGNS, TYPE A	675.20	0.5					
	210							210		LB	TUBULAR STEEL SIGN POST	675.33	6					
	2900	30						2930		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	45					
	2							2		EACH	FOUNDATION FOR TUBULAR STEEL POST	675.43	-					
	218	3						221		EACH	REMOVING SIGNS	675.50	-					
	53	3						56		EACH	ERECTING SALVAGED SIGNS	675.60	-					
	70							70		EACH	DELINEATOR WITH STEEL POST	676.10	3					
	17							17		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-					
	1							1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-					
	6							6		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620	-					
								125		SF	SPECIAL PROVISION (ASPHALTIC APPROACH MATERIAL)	900.670	5					
	4550							4550		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	69					
	100							100		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST					
	29900							29900		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	363.6					
											BEGIN ALTERNATE ZA1							
								4350		LF	SPECIAL PROVISION (GREGORY MINI SPACER GUARDRAIL)(W/ 8 FEET POSTS)	900.640	12.75					
								600		LF	SPECIAL PROVISION (GREGORY MINI SPACER GUARDRAIL)	900.640	21					
								525		LF	SPECIAL PROVISION (REMOVE AND RESET GUARDRAIL)(GMS GUARDRAIL)	900.640	12.5					
											END ALTERNATE ZA1							

PROJECT NAME: ENOSBURGH-RICHFORD  
 PROJECT NUMBER: STP 2969(I)  
 FILE NAME: z16vi04frm.dgn  
 PROJECT LEADER: G. EDWARDS  
 DESIGNED BY: D. BARNES  
 QUANTITY SHEET 3  
 PLOT DATE: 4/2/2018  
 DRAWN BY: D. BARNES  
 CHECKED BY: J. LITTLE  
 SHEET 24 OF 222

