STATION	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) (LB / FT) 1.75 / 1.88	2.00 / 2.42	2.50 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	3.50 / 9.00	4.00 / 10.80	5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
ENOSBURGH VT 105					FY- FLOURESCENT YELLOW FYG- FLOURESCENT YELLOW GREEN																						
E 79+26, LT	VR-038	24	18		STATE HIGHWAY ENDS	3.00								1		X											T-71
	R2-1	24	30		SPEED LIMIT 25	5.00																			X		
E 79+76, LT					Water Tower Rd				1	1				1		X											
					Elm St				1	1																	
	R1-1	30	30		STOP	6.25																			X		
	VD-700	6	10		1050 0603 0151	0.42																					T-44
E 80+27, RT	D3-1	36	8		Jayview Dr	2.00								1		X										149	
	R1-1	30	30		STOP	6.25																			X		
	VD-700	6	10		1050 0603 0152	0.42																					T-44
E 80+53, LT	D3-1	42	8		Sampsonville Rd	2.34								1		X										149	
E 81+47, RT	VR-039	24	18		STATE HIGHWAY BEGINS	3.00								1		X											T-71
	R2-1	24	30		SPEED LIMIT 30	5.00																			X		
E 84+48, RT	VD-700	6	10		1050 0603 0160	0.42								1	X												T-44
E 89+07, RT	R2-1	24	30		SPEED LIMIT 40	5.00								1		X									X		
E 92+75, LT	W3-5	36	36		WHEN FLASHING 30	9.00								2		X									X		
SIGN SUMMARY SHEET					SHEET TOTALS	48.10	0.00	0	2	2	0	0	0	9		128		0	0	0	0	0					
						SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION					TOWN TOTALS	213.19	0.00	0	23	23	0	0	0	78		1030		0	0	0	0	0					

PROJECT NAME: ENOSBURG-RICHFORD
PROJECT NUMBER: STP 2969(1)
FILE NAME: z16v104EnosburgTSSS.xls
PLOT DATE: 3/13/2018
PROJECT MANAGER: J. LITTLE
DRAWN BY: D. DRAPER
DESIGNED BY: D. DRAPER
CHECKED BY: J. LITTLE
TRAFFIC SIGN SUMMARY SHEET 1
SHEET 128 OF 222