STATION	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ENOSBURGH VT 105					FY- FLOURESCENT YELLOW FYG- FLOURESCENT YELLOW GREEN																						
E 95+10, RT	VD-701	6	10		BRIDGE 18 VT-105	0.42								1	X												T-42
E 95+25, LT	VD-701	6	10		BRIDGE 18 VT-105	0.42								1	X												T-42
	VD-700	6	10		1050 0603 0180	0.42																				T-44
E 99+51, LT					Berkson Farm B&B rt. on 108 ↑ 1				1	1				2		X								SALVAGE SIGNS ON NEW POSTS (NO FEDERAL PARTICIPATION)			
					St. Matthew's 105 to church st. ↑ 1				1	1																	
					Champlain Chevy left on missisquoi st. ← 1				1	1																	
E 105+60, LT	VD-700	6	10		1050 0603 0200	0.42								1	X												T-44
E 107+04, RT	R2-1	24	30		SPEED LIMIT 50	5.00								1		X										X	
E 108+99, LT	VD-018B	36	24		Enosburg Falls Sheldon Jct 9	6.00								1		X											T-95
E 110+99, LT	W3-5	36	36		SPEED 40	9.00								2		X										X	
E 115+33, RT	VD-701	6	10		BRIDGE 19 VT-105	0.42								1	X												T-42
E 115+47, LT	VD-701	6	10		BRIDGE 19 VT-105	0.42								1	X												T-42
E 116+16, RT	VD-700	6	10		1050 0603 0220	0.42								1	X												T-44
E 118+00, RT	VW-202	30	30		TRUCKS ENTERING	6.25								1		X											T-81
E 123+25, LT	VW-202	30	30		TRUCKS ENTERING	6.25								1		X											T-81
SIGN SUMMARY SHEET					SHEET TOTALS	35.44	0.00	0	3	3	0	0	0	14		168		0	0	0	0	0					
						SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION					TOWN TOTALS	213.19	0.00	0	23	23	0	0	0	78		1030		0	0	0	0	0					

PROJECT NAME: **ENOSBURG-RICHFORD**
PROJECT NUMBER: **STP 2969(1)**

FILE NAME: **z16v104EnosburaTSSS.xls** PLOT DATE: **3/13/2018**
PROJECT MANAGER: **J. LITTLE** DRAWN BY: **D. DRAPER**
DESIGNED BY: **D. DRAPER** CHECKED BY: **J. LITTLE**
TRAFFIC SIGN SUMMARY SHEET 2 SHEET **129** OF **222**