STATION	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL Ø (IN)					SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
						"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
ENOSBURGH VT 105					FY- FLOURESCENT YELLOW FYG- FLOURESCENT YELLOW GREEN																					
E 211+11, LT	VD-701	6	10		BRIDGE 21 VT-105	0.42								1	X											T-42
	VD-700	6	10		1050 0603 0400	0.42																				T-44
E 221+76, RT	VD-700	6	10		1050 0603 0420	0.42								1	X											T-44
E 232+32, LT	VD-700	6	10		1050 0603 0440	0.42								1	X											T-44
E 237+59, RT		18	24	WHT BRN	Pearl Harbor Memorial Highway	3.00								1		X									152	
E 242+88, RT	VD-700	6	10		1050 0603 0460	0.42								1	X											T-44
E 248+88, RT	W11-15a	30	30	FY	TRAIL CROSSING	6.25								1		X									X	
	W16-7P	24	12	FY		2.00																			X	
E 249+08, RT		18	18	BLK WHT	CROSS AT STOP SIGN	2.25								1		X								RAIL TRAIL SIGN		150	
E 250+08, LT	R1-1	18	18		STOP	2.25								1		X								RAIL TRAIL STOP SIGN	X		
E 250+22, RT	R1-1	18	18		STOP	2.25								1		X								RAIL TRAIL STOP SIGN	X		
E 250+48, LT		18	18	BLK WHT	CROSS AT STOP SIGN	2.25								1		X								RAIL TRAIL SIGN		150	
E 250+88, RT	W2-2	30	30	FY		6.25								1		X									X	
SIGN SUMMARY SHEET					SHEET TOTALS	28.60	0.00	0	0	0	0	0	0	11		137		0	0	0	0	0					
						SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION					TOWN TOTALS	213.19	0.00	0	23	23	0	0	0	78		1030		0	0	0	0	0					

PROJECT NAME: ENOSBURG-RICHFORD
PROJECT NUMBER: STP 2969(1)

FILE NAME: z16v104EnosburaTSSS.xls
PROJECT MANAGER: J. LITTLE
DESIGNED BY: D. DRAPER
TRAFFIC SIGN SUMMARY SHEET 6

PLOT DATE: 3/13/2018
DRAWN BY: D. DRAPER
CHECKED BY: J. LITTLE
SHEET 133 OF 222