STATION	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
BERKSHIRE VT 105					FY- FLOURESCENT YELLOW FYG- FLOURESCENT YELLOW GREEN																						
B 10+56, RT	VD-700	6	10		1050 0602 0020	0.42								1	X												T-44
B 16+85, RT	W1-4	30	30			6.25								1		X									X		
B 19+75, LT		18	18	BLK WHT	CROSS AT STOP SIGN	2.25								1		X								RAIL TRAIL SIGN		150	
B 21+01, RT					TRAIL CROSSING				1	1				1		X											
									1	1																	
B 21+20, RT	R1-1	18	18		STOP	2.25								1		X								RAIL TRAIL STOP SIGN	X		
B 21+31, LT	R1-1	18	18		STOP	2.25								1		X								RAIL TRAIL STOP SIGN	X		
B 21+75, RT		18	18	BLK WHT	CROSS AT STOP SIGN	2.25								1		X								RAIL TRAIL SIGN		150	
B 31+68, RT	VD-700	6	10		1050 0602 0060	0.42								1	X												T-44
B 40+13, LT					SPEED LIMIT 50				1	1				1		X											
B 42+24, LT	VD-700	6	10		1050 0602 0080	0.42								1	X												T-44
B 43+67, RT		18	18	BLK WHT	CROSS AT STOP SIGN	2.25								1		X								RAIL TRAIL SIGN		150	
B 44+32, RT	R1-1	18	18		STOP	2.25								1		X								RAIL TRAIL STOP SIGN	X		
	VD-701	6	10		BRIDGE 23 VT-105	0.42																					T-42
B 44+44, LT	VD-701	6	10		BRIDGE 23 VT-105	0.42																		INSTALL SIGN ON EXISTING POST BELOW EXISTING SIGNS			T-42
					SHEET TOTALS	21.85	0.00	0	3	3	0	0	0	12		159		0	0	0	0	0					
						SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
					TOWN TOTALS	205.49	0.00	0	33	33	0	0	0	100		1311		2	204	0	0	0					

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **ENOSBURG-RICHFORD**
PROJECT NUMBER: **STP 2969(1)**

FILE NAME: **z16v104BerkshireTSSS.xls**
PROJECT MANAGER: **J. LITTLE**
DESIGNED BY: **G. BURGMEIER**
TRAFFIC SIGN SUMMARY SHEET 8

PLOT DATE: **3/13/2018**
DRAWN BY: **G. BURGMEIER**
CHECKED BY: **J. LITTLE**
SHEET **135** OF **222**