STATION	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
						"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
RICHFORD VT 105					FY- FLOURESCENT YELLOW FYG- FLOURESCENT YELLOW GREEN																					
R 66+95, RT	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X										T-70
R 67+48, RT	R1-1	30	30		STOP	6.25								1		X								X		
	VD-700	6	10		1050 0611 0127	0.42																				T-44
R 68+75, LT	D3-1	66	12		Sewer Plant Rd PVT	5.50								2		X									152	
R 68+81, LT	R1-1	30	30		STOP	6.25								1		X								X		
	VD-700	6	10		1050 0611 0130	0.42																				T-44
R 69+04, RT	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								X		
R 69+24, LT	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X										T-70
R 69+50, LT	VD2-1S	72	20		Richford Elementary School	10.00								2		X										T-93
R 71+88, LT	S1-1	36	36	FYG	SCHOOL	9.00								1		X								X		
	S4-3P	24	8	FYG		1.34																		X		
R 73+92, RT	VD-700	6	10		1050 0611 0140	0.42								1	X											T-44
R 76+44, RT	W3-5	36	36		SPEED 25	9.00								2		X								X		
R 76+50, LT	D3-1	66	12		All Saints Cemetery	5.50								2		X									152	
SIGN SUMMARY SHEET					SHEET TOTALS	69.10	0.00	0	0	0	0	0	0	15		218		0	0	0	0	0				
						SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION					TOWN TOTALS	181.82	0.00	0	0	0	0	0	0	40		544		0	0	0	0	0				

PROJECT NAME: ENOSBURG-RICHFORD
PROJECT NUMBER: STP 2969(1)

FILE NAME: z16v104RichfordTSSS.xls
PROJECT MANAGER: J. LITTLE
DESIGNED BY: G. BURGMEIER
TRAFFIC SIGN SUMMARY SHEET 18

PLOT DATE: 3/13/2018
DRAWN BY: G. BURGMEIER
CHECKED BY: J. LITTLE
SHEET 145 OF 222