

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
							ROADWAY	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							6			6		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-			YIELDING MARKER POSTS
							79			79		EACH	YIELDING MARKER POSTS	619.17	EST	49	EACH	EXISTING DRAINAGE
							375			375		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	7	30	EACH	UNDERDRAIN
							250			250		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	25	-	EACH	ROUNDING
							150			150		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	2.5	79	EACH	TOTAL
							170			170		EACH	STEEL BEAM GUARDRAIL DELINEATOR	621.218	9			
							9			9		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
							5025			5025		LF	REMOVE AND RESET GUARDRAIL	621.75	18.5			
							200			200		EACH	REPLACE GUARDRAIL POST ASSEMBLY	621.76	EST			
							100			100		EACH	REPLACE GUARDRAIL BEAM UNIT	621.77	EST			
							475			475		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	12.5			
							400			400		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
							1500			1500		HR	FLAGGERS	630.15	EST			
									0.2	0.2		LS	FIELD OFFICE, ENGINEERS	631.10	-			
									0.2	0.2		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
									0.2	0.2		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
									600	600		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
							0.2			0.2		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							1			1		LS	TRAFFIC CONTROL (STP 2916(1))	641.10	-			
							2			2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
							1400			1400		LF	DURABLE 4 INCH WHITE LINE, TYPE A TAPE	646.4011	43			
													BEGIN OPTION CC					
							17400			17400		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	195			
							17400			17400		LF	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	646.403	195			
							17400			17400		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	195			
													END OPTION CC					
							1600			1600		LF	DURABLE 4 INCH YELLOW LINE, TYPE A TAPE	646.4111	32			
													BEGIN OPTION DD					
							17600			17600		LF	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	646.413	172			
							17600			17600		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	172			
													END OPTION DD					
							15			15		LF	DURABLE 24 INCH STOP BAR, TYPE A TAPE	646.4811	2			
													BEGIN OPTION FF					
							135			135		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	4			
							135			135		LF	DURABLE 24 INCH STOP BAR, EPOXY PAINT	646.483	4			
							135			135		LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	4			
													END OPTION FF					
							4			4		EACH	DURABLE LETTER OR SYMBOL, TYPE D TAPE	646.4914	-			

PROJECT NAME: RICHFORD  
 PROJECT NUMBER: STP 2916(I)  
 FILE NAME: z10c234frm.dgn  
 PROJECT LEADER: G. EDWARDS  
 DESIGNED BY: G. BURGMEIER  
 QUANTITY SHEET 2  
 PLOT DATE: 4/2/2018  
 DRAWN BY: G. BURGMEIER  
 CHECKED BY: J. LITTLE  
 SHEET 171 OF 222

