STATION	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
RICHFORD VT 105A																											
77+63, RT	VD1-1A	72	12		East Richford 1	6.00								2		X											T-93
78+00, LT	M3-3	24	12	GRN WHT	SOUTH VERMONT 105A	2.00								1		X									X		
	M1-5	30	24	GRN WHT		5.00																					E-136B
79+56, RT	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X											T-70
79+81, RT	R1-1	30	30		STOP	6.25								1		X									X		
	VD-700	6	10		1051 0611 0151	0.42																					T-44
80+02, RT	D3-1	72	12		E Richford Slide Rd	6.00								2		X										219	
80+82, LT	W12-2	36	36	FY	12'-0"	9.00								2			X							INSTALL POSTS USING 2 1/2" SOIL BEARING SLIP BASES (SEE SHEET 215)	X		
	W12-2	36	36	FY	3.6m	9.00																		METRIC WARNING SIGN	X		
	M6-1	21	15	FY		2.19																			X		
81+74, RT	M3-1	24	12	GRN WHT	NORTH VERMONT 105A	2.00								1		X									X		
	D1-5	30	24	GRN WHT		5.00																					E-136B
81+82, LT	VD1-1A	72	12		East Richford 1	6.00								2		X											T-93
84+00, LT	VD-421	60	48	GRN WHT	Welcome To VERMONT THE GREEN MOUNTAIN STATE	20.00								2			X							INSTALL POSTS USING 2 1/2" SOIL BEARING SLIP BASES (SEE SHEET 215)		219	
	VD-700	6	10		1051 0611 0160	0.42																					T-44
SIGN SUMMARY SHEET					SHEET TOTALS	84.28	0.00	0	0	0	0	0	0	14		150	60	0	0	0	0	0					
						SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION					TOWN TOTALS	448.84	0.00	0	2	2	0	0	0	75		1083		0	0	0	0	0					

PROJECT NAME: **RICHFORD**
PROJECT NUMBER: **STP 2916(1)**

FILE NAME: **z10c234TSSS.xls** PLOT DATE: **3/13/2018**
PROJECT MANAGER: **G. EDWARDS** DRAWN BY: **G. BURGMEIER**
DESIGNED BY: **G. BURGMEIER** CHECKED BY: **J. LITTLE**
TRAFFIC SIGN SUMMARY SHEET 6 SHEET **215** OF **222**