

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								480			480		CY	COMMON EXCAVATION	203.15				
								620			620		CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28				
								6			6		CY	TRENCH EXCAVATION OF EARTH	204.20				
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								25			25		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
								30			30		CWT	EMULSIFIED ASPHALT	404.65				
								1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								4			4		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40				
								330			330		LF	REMOVAL OF EXISTING CURB	616.41				
								145			145		LF	REMOVAL OF EXISTING FENCE	620.55				
								265			265		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
								720			720		HR	FLAGGERS	630.15				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
								1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
								1			1		LS	TRAFFIC CONTROL	641.10				
								2			2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
								3525			3525		LF	DURABLE 4 INCH WHITE LINE	646.400				
								8			8		EACH	DURABLE LETTER OR SYMBOL	646.490				
								95			95		LF	TEMPORARY 4 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6011				
								14			14		EACH	TEMPORARY LETTER OR SYMBOL, TEMPORARY PAVEMENT MARKING TAPE	646.6911				
								300			300		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
									2		2		LB	SEED	651.15				
									10		10		LB	FERTILIZER	651.18				
									1		1		TON	AGRICULTURAL LIMESTONE	651.20				
									1		1		TON	HAY MULCH	651.25				
									5		5		CY	TOPSOIL	651.35				
									715		715		LF	PROJECT DEMARCATION FENCE	653.55				
								66			66		SF	TRAFFIC SIGNS, TYPE A	675.20				
								75			75		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
								2			2		EACH	ERECTING SALVAGED SIGNS	675.60				
								3			3		EACH	SETTING SALVAGED POSTS	675.61				
								14			14		LF	WIRED CONDUIT (2")(PVC)(SCH. 80)	678.23				
								6100			6100		LF	ELECTRICAL WIRING	678.24				
								1			1		EACH	PULL BOX, STANDARD	678.25				
								1			1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
								5			5		EACH	SPECIAL PROVISION (ADJUSTING ELEVATION OF MONITORING WELLS)	900.620				
								7			7		EACH	SPECIAL PROVISION (ELECTRIC VEHICLE OUTLET, LEVEL 1)	900.620				
								100			100		GAL	SPECIAL PROVISION (FLUSHING AND CLEANING UNDERDRAINS AND DRAINAGE STRUCTURES)	900.625				
								145			145		LF	SPECIAL PROVISION (SPLIT RAIL FENCE)	900.640				
								1			1		LS	SPECIAL PROVISION (ASPHALT FIELD PERMEAMETER KIT)	900.645				

PROJECT NAME: RANDOLPH PARK AND RIDE LOT
 PROJECT NUMBER: CMG PARK (02) C/2
 FILE NAME: z17c060qs.dgn PLOT DATE: 6/15/2017
 PROJECT LEADER: S.E. BURBANK DRAWN BY: M.F. SUFFEL
 DESIGNED BY: E.P. DETRICK CHECKED BY: J.D. KEENER
 QUANTITY SHEET (1 OF 2) SHEET 6 OF 15

