

TRAFFIC DATA

VT ROUTE 44	AADT		DHV		ESAL'S	ESAL'S
	2018	2028	2018	2028	2018-2028	2018-2038
BEGIN PROJECT TO RUSH MEADOW RD. (MM 0.000 - MM 1.068)	860	890	120	200	126,000	284,000
RUSH MEADOW RD. TO BROWNSVILLE-HARTLAND RD. (MM 1.068 - MM 4.082)	1700	1800	200	210	252,000	576,000
BROWNSVILLE-HARTLAND RD. TO END PROJECT (MM 4.082 - MM 1.607)	1,900	2,000	220	230	199,000	445,000

SUPERPAVE BITUMINOUS CONCRETE PAVEMENT MIXTURE DESIGN CRITERIA	
DESIGN LANE/DESIGN LIFE ESALS	311,040
DESIGN NUMBER OF GYRATIONS	50
PERFORMANCE GRADE ASPHALT BINDER	70-28

PROJECT NAME:	READING-WINDSOR
PROJECT NUMBER:	STP FPAV(11)
FILE NAME:	COMP. STP FPAV(11),(12) & (13).dgn
PLOT DATE:	04-APR-2018
PROJECT LEADER:	B. KIPP
DRAWN BY:	L. BULLOCK
DESIGNED BY:	L. BULLOCK
CHECKED BY:	B. KIPP
PROJECT INFORMATION SHEET	SHEET 10 OF 53