

**PROJECT PAVING LIMITS**

TOWN AND ROUTE	BEGIN STATION	END STATION	LANE TYPICAL	WEARING DEPTH	LEVELING DEPTH	NOTES
VT. RTE. 44						
READING						
	0.000	0.162	6' - 11' - 11' - 6'	1 1/2"	3/4"	LEVEL AND OVERLAY
	0.162	0.202	VARIES- 11' - 11' - VARIES	1 1/2"	3/4"	LEVEL AND OVERLAY
WEST WINDSOR						
	WW 0.000	WW 1.100	1.5' - 11' - 11' - 1.5'	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 1.100	WW 1.200	VARIES' - 11' - 11' - VARIES	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 1.200	WW 2.381	2' - 11' - 11' - 2'	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 2.381	WW 2.482	VARIES- 11' - 11' - VARIES	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 2.482	WW 2.944	1.5' - 11' - 11' - 1.5'	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 2.944	WW 3.044	VARIES- 11' - 11' - VARIES	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 3.044	WW 3.502	2.5' - 11' - 11' - 2.5'	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 3.502	WW 3.536	VARIES- 11' - 11' - VARIES	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 3.536	WW 3.707	3' - 11' - 11' - 3'	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 3.707	WW 3.986	4' - 11' - 11' - 3'	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 3.986	WW 3.980	VARIES- 11' - 11' - VARIES	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 3.980	WW 4.099	8' - 11' - 11' - 8'	1 1/2"	1/2"	COLD PLANE 2" ; LEVEL AND OVERLAY
	WW 4.099	WW 4.113	VARIES- 11' - 11' - VARIES	1 1/2"	1/2"	COLD PLANE 2" ; LEVEL AND OVERLAY
	WW 4.113	WW 4.138	4' - 11' - 11' - 4'	1 1/2"	1/2"	COLD PLANE 2" ; LEVEL AND OVERLAY
	WW 4.138	WW 4.157	VARIES- 11' - 11' - VARIES	1 1/2"	1/2"	COLD PLANE 2" ; LEVEL AND OVERLAY
	WW 4.157	WW 4.352	7' - 11' - 11' - 7'	1 1/2"	1/2"	COLD PLANE 2" ; LEVEL AND OVERLAY
	WW 4.352	WW 4.367	VARIES- 11' - 11' - VARIES	1 1/2"	1/2"	COLD PLANE 2" ; LEVEL AND OVERLAY
	WW 4.367	WW 4.430	1.5' - 11' - 11' - 1.5'	1 1/2"	1/2"	COLD PLANE 2" ; LEVEL AND OVERLAY
	WW 4.430	WW 4.616	1.5' - 11' - 11' - 1.5'	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 4.616	WW 4.636	VARIES- 11' - 11' - VARIES	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 4.636	WW 4.656	3' - 11' - 11' - 10' - 3'	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 4.656	WW 4.735	VARIES- 11' - 11' - VARIES	1 1/2"	3/4"	LEVEL AND OVERLAY
	WW 4.735	WW 5.044	1.5' - 11' - 11' - 1.5'	1 1/2"	3/4"	LEVEL AND OVERLAY
WINDSOR						
	WI 0.000	WI 1.607	1.5' - 11' - 11' - 1.5'	1 1/2"	3/4"	LEVEL AND OVERLAY

PROJECT NAME:	READING-WINDSOR
PROJECT NUMBER:	STP FPAV(11)
FILE NAME:	COMP.STP FPAV(11),(12) & (13).dgn
PLOT DATE:	04-APR-2018
PROJECT LEADER:	B. KIPP
DRAWN BY:	L. BULLOCK
DESIGNED BY:	L. BULLOCK
CHECKED BY:	B. KIPP
TYPICAL AND DETAIL SHEET 2	SHEET 12 OF 53