

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
					ROADWAY	ROADWAY (NO FEDERAL/STA)	BRIDGE	FULL C&E	ROADWAY	ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					580						580		CY	EARTH BORROW	203.30	EST.			
					8750						8750		LF	SHOULDER BERM REMOVAL	203.40	38			COLD PLANING, BITUMINOUS PAVEMENT
					1						1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	9051	SY	MAINLINE
					12320						12320		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	107	328	SY	APPROACHES
					690						690		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	EST	546	SY	TOWN HIGHWAYS
														BEGIN OPTION AA			2267	SY	BRIDGES
					1170						1170		CWT	EMULSIFIED ASPHALT	404.65	9	128	SY	RND.
					1170						1170		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	9	12,320	SY	TOTAL
														END OPTION AA					
					1						1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
							240				240		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	7			
							100				100		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.			
					2						2		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-			
						2					2		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-			
					110						110		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
					50						50		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
					100						100		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			
					220						220		HR	TRUCK RENTAL	608.37	EST.			
					40						40		HR	LOADER RENTAL, TYPE I	608.40	EST.			
					10						10		CY	STONE FILL, TYPE I	613.10	EST.			
					1150						1150		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	11			
					4400						4400		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	-			
					225						225		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.217	-			
					21						21		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
					47						47		EACH	REPLACE GUARDRAIL POST ASSEMBLY	621.76	-			
					3						3		EACH	REPLACE GUARDRAIL BEAM UNIT	621.77	-			
					625						625		LF	ADJUST HEIGHT OF GUARDRAIL	621.79	12.5			
					5700						5700		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	50			
					700						700		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
					2800						2800		HR	FLAGGERS	630.15	EST.			
								0.33			0.33		LS	FIELD OFFICE, ENGINEERS	631.10	-			
								0.3			0.3		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
								0.3			0.3		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
								1000			1000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
					0.4						0.4		LS	MOBILIZATION/DEMobilIZATION	635.11	-			
					1						1		LS	TRAFFIC CONTROL (STP FPAV(11))	641.10	-			
					4						4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			

PROJECT NAME: READING-WINDSOR
PROJECT NUMBER: STP FPAV(II)
FILE NAME: COMP, STP FPAV(II),(I2) & (I3).dgn PLOT DATE: 04-APR-2018
PROJECT LEADER: B. KIPP DRAWN BY: N. PAPPAS
DESIGNED BY: N. PAPPAS CHECKED BY: B. KIPP
QUANTITY SHEET I SHEET 14 OF 53