

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	ROADWAY (NO FEDERAL/STA)	BRIDGE	FULL C&E	ROADWAY	ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
														BEGIN OPTION BB					
					72200						72200		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	232			
					72200						72200		LF	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	646.403	232			
					72200						72200		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	232			
														END OPTION BB					
														BEGIN OPTION CC					
					71100						71100		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	252	12842	TON	MAINLINE (2 1/4" TYPE IVS)
					71100						71100		LF	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	646.413	252	1052	TON	MAINLINE (2" TYPE IVS)
					71100						71100		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	252	136	TON	RND.
														END OPTION CC					
														BEGIN OPTION DD					
					25						25		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	3			
					25						25		LF	DURABLE 24 INCH STOP BAR, EPOXY PAINT	646.483	3			
					25						25		LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	3			
														END OPTION DD					
														BEGIN OPTION EE					
					13						13		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-			
					13						13		EACH	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493	-			
					13						13		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-			
														END OPTION EE					
					77000						77000		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	232			
					75880						75880		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	252			
					25						25		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	3			
					13						13		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
					14620						14620		EACH	LINE STRIPING TARGETS	646.76	146			
					25						25		LB	SEED	651.15	EST.			
					80						80		LB	FERTILIZER	651.18	EST.			
					1						1		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
					1						1		TON	HAY MULCH	651.25	EST.			
					105						105		CY	TOPSOIL	651.35	EST.			
					575						575		SY	TEMPORARY EROSION MATTING	653.20	EST.			
					40						40		EACH	DELINEATOR WITH STEEL POST	676.10	2			
					40						40		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	2			
					200						200		EACH	REMOVE AND REPLACE REFLECTOR UNIT	676.15	EST.			
					1						1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
					1150						1150		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	17			
					1100						1100		TON	SPECIAL PROVISION (AGGREGATE SHOULDERS, RAP WITH RAS)	900.680	6			
					50						50		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.			
					14030						14030		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	136			

THIS ITEM WAS MODIFIED BY CHANGE ORDER #1: The contractor requested the use of PG 58-28 asphalt in the Hand-Placed Bituminous mix used for hand paving aprons at a reduced cost instead of the PG 70-28 asphalt, per contract. The PG 70-28 asphalt is only made with a polymer which results in a workability that does not leave a desirable looking mat when not placed by a paver screed.

PROJECT NAME:	READING-WINDSOR
PROJECT NUMBER:	STP FPAV(II)
FILE NAME: COMP, STP FPAV(II),(I2) & (I3).dgn	PLOT DATE: 04-APR-2018
PROJECT LEADER: B. KIPP	DRAWN BY: N. PAPPAS
DESIGNED BY: N. PAPPAS	CHECKED BY: B. KIPP
QUANTITY SHEET 2	SHEET 15 OF 53