

TRAFFIC DATA

VT ROUTE 44	AADT		DHV		ESAL'S	ESAL'S
	2018	2028	2018	2028	2018-2028	2018-2038
BEGIN PROJECT TO KNAPP BROOK ROAD (MM 4.290 - MM 0.150)	1,600	1,700	190	200	204,000	463,000
KNAPP BROOK ROAD TO VT ROUTE 44 (MM 0.150 - MM 1.812)	1,500	1,600	200	210	287,000	631,000
VT ROUTE 44 TO END OF PROJECT (MM 1.812 - MM 7.277)	1,100	1,200	160	170	160,000	371,000

SUPERPAVE BITUMINOUS CONCRETE PAVEMENT MIXTURE DESIGN CRITERIA	
DESIGN LANE/DESIGN LIFE ESALS	321,810
DESIGN NUMBER OF GYRATIONS	50
PERFORMANCE GRADE ASPHALT BINDER	70-28

PROJECT NAME:	WEATHERSFIELD-READING
PROJECT NUMBER:	STP FPAV(12)
FILE NAME: COMP. STP FPAV(11),(12) & (13).dgn	PLOT DATE: 04-APR-2018
PROJECT LEADER: B. KIPP	DRAWN BY: N. PAPPAS
DESIGNED BY: N. PAPPAS	CHECKED BY: B. KIPP
PROJECT INFORMATION SHEET	SHEET 30 OF 53