

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
						ROADWAY	BRIDGE	FULL C.E.	ROADWAY (ALTERNATE ZA1)	ROADWAY (ALTERNATE ZA2)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
						112900					112900		LF	BEGIN OPTION CC						ALTERNATE ZA1
						112900					112900		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	351	15,027 TON		TYPE IV, WEARING COURSE	
						112900					112900		LF	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	646.413	351	7,304 TON		TYPE IV, LEVELING COURSE	
						112900					112900		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	351	22,331 TON		SUBTOTAL	
														END OPTION CC			269 TON		ROUNDING	
														BEGIN OPTION DD			22,600 TON		TOTAL	
						80					80		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	-	15,027 TON		ALTERNATE ZA2	
						80					80		LF	DURABLE 24 INCH STOP BAR, EPOXY PAINT	646.483	-	7,304 TON		TYPE IV, WEARING COURSE	
						80					80		LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	-	22,331 TON		SUBTOTAL	
														END OPTION DD			269 TON		ROUNDING	
														BEGIN OPTION EE			22,600 TON		TOTAL	
						8					8		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-				
						8					8		EACH	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493	-				
						8					8		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-				
														END OPTION EE						
						123470					123470		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	351				
						123470					123470		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	351				
						160					160		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	-				
						8					8		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-				
						22900					22900		EACH	LINE STRIPING TARGETS	646.76	449				
						40					40		LB	SEED	651.15	EST				
						100					100		LB	FERTILIZER	651.18	EST				
						1					1		TON	AGRICULTURAL LIMESTONE	651.20	EST				
						1					1		TON	HAY MULCH	651.25	EST				
						145					145		CY	TOPSOIL	651.35	EST				
						710					710		SY	TEMPORARY EROSION MATTING	653.20	EST				
						86					86		EACH	DELINEATOR WITH STEEL POST	676.10	EST				
						86					86		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	EST				
						525					525		EACH	REMOVE AND REPLACE REFLECTOR UNIT	676.15	EST				
						1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-				
						1650					1650		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	EST				
						1950					1950		TON	SPECIAL PROVISION (AGGREGATE SHOULDERS, RAP WITH RAS)	900.680	EST				
						100					100		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST				
						22600					22600		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	269				
														BEGIN ALTERNATE ZA1						
									22600		22600		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT (PG 70-28)(SBS POLYMER)	406.27	269				
									1		1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	406.28	-				
														END ALTERNATE ZA1						

THIS ITEM WAS MODIFIED BY CHANGE ORDER #1: The contractor requested the use of PG 58-28 asphalt in the Hand-Placed Bituminous mix used for hand paving aprons at a reduced cost instead of the PG 70-28 asphalt, per contract. The PG 70-28 asphalt is only made with a polymer which results in a workability that does not leave a desirable looking mat when not placed by a paver screed.

PROJECT NAME:	WEATHERSFIELD-READING
PROJECT NUMBER:	STP FPAV(I2)
FILE NAME: COMP, STP FPAV(I1,I2) & (I3).dgn	PLOT DATE: 04-APR-2018
PROJECT LEADER: B. KIPP	DRAWN BY: N. PAPPAS
DESIGNED BY: N. PAPPAS	CHECKED BY: B. KIPP
QUANTITY SHEET 2	SHEET 35 OF 53