ITEM DETAIL SHEET 1

LOCATION			203.30	621.20	621.205	621.617	621.60	621.76	621.77	621.79	621.80	651.35	653.20	676.10	676.12	676.15								REMARKS
MM	MM	POS	EARTH BORROW	STEEL BEAM GUARDRAIL GALV.	STEEL BEAM GUARDRAIL GALV. W/8 FEET POSTS	HD STEEL BEAM GUARDRAIL, GALVANIZED/ NESTED W/8 FEET POSTS	ANCHOR FOR STEEL BEAM RAIL	REPLACE GUARDRAIL POST ASSEMBLY	REPLACE GUARDRAIL BEAM ASSEMBLY	ADJUST HEIGHT OF GUARDRAIL	REMOVAL AND DISPOSAL OF GUARDRAIL	TOPSOIL	TEMP. EROSION MATTING	DELIN. W/STEEL POST	REMOVAL OF EXIST. DELIN.	REMOVE AND REPLACE REFLECTOR UNIT								
			CY	LF	LF	LF	EACH	EACH	EACH	LF	LF	CY	SY	EACH	EACH	EACH								
																525								ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER
	WEATHERSFIELD																							
5.593	5.608	LT		39.00			2				37.50			2	2									REMOVE MELT, SEE STANDARD G-1D
5.593	5.623	RT		78.00			2				75.00			2	2									REMOVE MELT, SEE STANDARD G-1D
6.877	6.952	RT		78.00			2				75.00			2	2									REMOVE MELT, SEE STANDARD G-1D
	CAVENDISH																							
0.020	0.267	RT		39.00			1	3	1	1299.00	37.50			2	2									REMOVE MELT, SEE STANDARD G-1D
0.340	0.367	RT								150.00				2	2									
	READING																							
0.112	0.117	LT	25.00	78.00			2				31.25	5.00	25.00	2	2									REMOVE MELT, SEE STANDARD G-1D
0.112	0.132	RT		100.00			2				75.00			2	2									REMOVE MELT, SEE STANDARD G-1D
0.561	0.580	RT	25.00	39.00			1				37.50	5.00	25.00	2	2									REMOVE MELT, SEE STANDARD G-1D
0.580	0.581	LT												2	2									
0.589	0.590	RT												2	2									
0.590	0.591	LT												2	2									
1.372	1.441	RT						1						2	2									
1.865	2.044	RT	50.00	78.00			2			950.00	75.00	10.00	50.00	2	2									REMOVE MELT, SEE STANDARD G-1D
2.208	2.233	RT	50.00	78.00			2				62.50	10.00	50.00	2	2									REMOVE MELT, SEE STANDARD G-1D
2.213	2.233	LT	25.00	39.00			1				25.00	5.00	10.00	2	2									REMOVE MELT, SEE STANDARD G-1D
2.851	2.896	LT						1		237.50				2	2									
2.950	3.005	LT	50.00	78.00			2				75.00	10.00	50.00	2	2									REMOVE MELT, SEE STANDARD G-1D
3.234	3.279	RT	25.00	115.50		100.00	2				212.50	5.00	25.00	2	2									REMOVE MELT'S, SEE STANDARD G-1D & S-366
3.249	3.324	LT	25.00	315.50		100.00	2	2			412.50	5.00	25.00	2	2									REMOVE MELT'S, SEE STANDARD G-1D & S-366
3.657	3.752	RT	50.00	78.00			2		2	506.25	75.00	10.00	50.00	2	2									REMOVE MELT, SEE STANDARD G-1D
3.937	4.121	RT	50.00	78.00			2			975.00	75.00	10.00	50.00	2	2									REMOVE MELT, SEE STANDARD G-1D
4.200	4.290	RT	50.00	78.00			2			475.00	75.00	10.00	50.00	2	2									REMOVE MELT, SEE STANDARD G-1D
4.464	4.569	RT	50.00	78.00			2			556.25	75.00	10.00	50.00	2	2									REMOVE MELT, SEE STANDARD G-1D
4.524	4.763	LT	25.00	39.00			1		5		37.50	5.00	25.00	2	2									REMOVE MELT, SEE STANDARD G-1D
4.773	4.883	LT	25.00	39.00			1			581.25	37.50	5.00	25.00	2	2									REMOVE MELT, SEE STANDARD G-1D
4.886	5.037	LT							3	800.00				2	2									
5.042	5.251	LT	50.00		1106.25		2				1106.25	10.00	50.00	2	2									REMOVE MELT, SEE STANDARD G-1D
5.186	5.371	RT	50.00		887.50		2			100.00	987.50	10.00	50.00	2	2									RETAIN 100 FEET, REMOVE MELT'S, SEE STANDARD G-1D
5.410	5.545	RT		78.00			2		2		75.00			2	2									REMOVE MELT, SEE STANDARD G-1D
5.570	5.654	RT	25.00	78.00			2				75.00	5.00	25.00	2	2									REMOVE MELT, SEE STANDARD G-1D
5.699	5.814	RT	25.00	39.00			1			618.75	37.50	5.00	25.00	2	2									REMOVE MELT, SEE STANDARD G-1D
5.809	6.023	LT	25.00	78.00			2			1131.25	75.00	5.00	25.00	2	2									REMOVE MELT, SEE STANDARD G-1D
6.087	6.098	LT						1	1	75.00				2	2									
6.087	6.103	RT						3	2	87.50				2	2									
6.108	6.181	RT						2	1					2	2									
6.172	6.192	LT	25.00	39.00			1	1		106.25	37.50	5.00	25.00	2	2									REMOVE MELT, SEE STANDARD G-1D
6.182	6.277	RT												2	2									
6.198	6.237	LT		39.00			1			206.25	37.50			2	2									REMOVE MELT, SEE STANDARD G-1D
6.262	6.282	LT		39.00			1			106.25	37.50			2	2									REMOVE MELT, SEE STANDARD G-1D
6.282	6.560	RT						8	4	1468.75				2	2									
6.566	6.690	RT		39.00			1	6	5	656.25	37.50			2	2									REMOVE MELT, SEE STANDARD G-1D
6.904	6.989	RT		78.00			2		1	450.00	75.00			2	2									REMOVE MELT, SEE STANDARD G-1D
6.905	7.138	LT		39.00			1		1		37.50			2	2									REMOVE MELT, SEE STANDARD G-1D
	SUBTOTAL		725.00	2091.00	1993.75	200.00	51	28	28	11536.50	4225.00	145.00	710.00	86	86	525								
	TOTAL ROUNDING		EST	EST	EST	-	EST	EST	EST	EST	EST	EST	EST	-	-	EST								
	PROJECT TOTAL		725.00	2091.00	1993.75	200.00	51	28	28	11536.50	4225.00	145.00	710.00	86	86	525								

PROJECT NAME: WEATHERSFIELD-READING
PROJECT NUMBER: STP FPAV(12)

FILE NAME: COMP. STP FPAV(11),(12) & (13).dgn PLOT DATE: 04-APR-2018
PROJECT LEADER: B. KIPP DRAWN BY: N. PAPPAS
DESIGNED BY: N. PAPPAS CHECKED BY: B. KIPP
ITEM DETAIL SHEET SHEET 37 OF 53