

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
						ROADWAY	BRIDGE	FULL C&E	ROADWAY	ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
														END OPTION CC						
														BEGIN OPTION DD						
						45					45		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	1				
						45					45		LF	DURABLE 24 INCH STOP BAR, EPOXY PAINT	646.483	1				
						45					45		LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	1			MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT OR SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	
														END OPTION DD						
														BEGIN OPTION EE						
						26					26		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-	5533 TON	MAINLINE		
						26					26		EACH	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493	-	8 TON	TOWN HIGHWAYS		
						26					26		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-	39 TON	RND.		
														END OPTION EE					5580 TON	TOTAL
						31670					31670		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	237				
						31700					31700		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	243				
						45					45		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	1				
						26					26		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-				
						6400					6400		EACH	LINE STRIPING TARGETS	646.76	77				
						15					15		LB	SEED	651.15	EST.				
						40					40		LB	FERTILIZER	651.18	EST.				
						1					1		TON	AGRICULTURAL LIMESTONE	651.20	EST.				
						1					1		TON	HAY MULCH	651.25	EST.				
						30					30		CY	TOPSOIL	651.35	EST.				
						150					150		SY	TEMPORARY EROSION MATTING	653.20	EST.				
						8					8		EACH	DELINEATOR WITH STEEL POST	676.10	-				
						8					8		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-				
						34					34		EACH	REMOVE AND REPLACE REFLECTOR UNIT	676.15	EST				
						1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-				
						450					450		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	13				
						500					500		TON	SPECIAL PROVISION (AGGREGATE SHOULDERS, RAP WITH RAS)	900.680	3				
						50					50		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.				
						5580					5580		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	39				
														BEGIN ALTERNATE ZA1						
									5580		5580		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT (PG 70-28)(SBS POLYMER)	406.27	39				
									1		1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	406.28	-				
														END ALTERNATE ZA1						
														BEGIN ALTERNATE ZA2						
										5580	5580		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 70-28)(SBS POLYMER)	490.30	39				
										1	1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-				
														END ALTERNATE ZA2						

THIS ITEM WAS MODIFIED BY CHANGE ORDER #1: The contractor requested the use of PG 58-28 asphalt in the Hand-Placed Bituminous mix used for hand paving aprons at a reduced cost instead of the PG 70-28 asphalt, per contract. The PG 70-28 asphalt is only made with a polymer which results in a workability that does not leave a desirable looking mat when not placed by a paver screed.

PROJECT NAME:	WEATHERSFIELD-WINDSOR
PROJECT NUMBER:	STP FPAV(I3)
FILE NAME: COMP, STP FPAV(I1),(I2) & (I3).dgn	PLOT DATE: 04-APR-2018
PROJECT LEADER: B. KIPP	DRAWN BY: N. PAPPAS
DESIGNED BY: N. PAPPAS	CHECKED BY: B. KIPP
QUANTITY SHEET 2	SHEET 47 OF 53