WOOD GUARD RAIL REQUIRED

LEFT

Sta. 871+43 to 871+73 Length 24 ft.

RIGHT

Sta. 871+43 to 871+73 Length 24 ft.

NEW CULVERTS REQUIRED

Sta 871+61 - 18" Reinf. Concrete Pipe Culvert 32 ft.
Concrete Class B. (1-2-4) 2.7 Cu. Yds.
Reinforcing Steel 53 pounds.

SUB-BASE OF GRAVEL REQUIRED

Sta. 866+00 to 882+00 - 9" Sub-base of gravel 1600 tons

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
9	VT.	72 S	1958	30	104

Record Plan Additions
Stop at Sta 866+00
August 9 1954
F.W. Aylett

Sta. 871+61 Old 18" C.M.P. Replace with 18" Reinf. Concrete Pipe See Series S-17

ROWLAND ROBINSON

ERNEST DEVINE

S 33°17' W.

866 867 868 869 870 871 872 873 874 875 876 877 878 879 880 881 882

B.M. 107
20" White Ash. Elev. 189.82

B. PARKER

ERNEST DEVINE

House

House

+0.20%
Sta. 867+50
200' V.C.
Elev. 192.40
-0.755%
Sta. 872+00
2.50' V.C.
Elev. 189.00
+1.066%
Sta. 875+00
200' V.C.
Elev. 192.20
+1.877%
Sta. 881+50
200 V.C.
Elev. 204.40

9" Subbase of Gravel

192.10	192.20	192.24	192.16	191.96	191.65	191.27	190.89	190.51	190.13	189.76	189.61	189.37	189.57	189.74	190.09	190.60	191.13	191.72	192.40	193.19	193.94	194.61	195.01	195.45	196.01	196.69	197.83	198.77	199.70	200.64	201.58	202.52	203.35	203.95	204.34
866+00	+50	867+00	+50	868+00	+50	869+00	+50	870+00	+50	871+00	+50	rd	872+00	+50	873+00	+50	874+00	+50	875+00	+50	876+00	+50	877+00	+50	878+00	+50	879+00	+50	880+00	+50	881+00	+50	882+00

B.M. No. 107 Spike in 20" White Ash Right of Sta. 868+46 Elev. 189.82

Series F No. 72 S
Sheet 30 of 104