EARTHWORK

V.C.	% GRD	STATION	GRADES ELEVATION ON TAN.	GRADES ELEVATION ON V.C.	CORR. V.C.	DIST.	AREA	CU. YDS.	AREA	CU. YDS.	AREA	CU. YDS.	AREA	CU. YDS.

BRIDGE QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION
STRUCTURES DIVISION

NO.	ITEM	UNIT	QUANTITY BREAKDOWN: Box	Wing-Walls	Channel	TOTAL	FINAL
202.25	Removal of Structure	EA	1			1	
203.27	Unclassified Channel Excavation	C.Y.			25	25	
204.25	Structure Excavation	C.Y.	70	45		115	
204.30	Granular Backfill for Structures	C.Y.	20	50		70	
406.25	Bituminous Concrete Pavement	TON	11			11	
501.25	Concrete, Class B	C.Y.	96	27		123	
507.15	Reinforcing Steel	lb	13714	2909		16623	
514.10	Water Repellent	GAL.	2	2		4	
519.20	Sheet Membrane Waterproofing	S.Y.	73			73	
613.11	Stone Fill, Type II	C.Y.			15	15	
617.30	Bridge Railing GALVANIZED BOX BEAM	L.F.	41			41	
638.11	Two-Way Temporary Bridge	L.S.			1	1	

BRIDGE (S) AT STATION (8) 21+50
LOCATION (8) VT. 116 OVER PATRICK BROOK

Prepared by: M. EVANS
Checked by: T.A. HOLLAR
SUPERVISOR: E.L. Outka 10-26

HINESBURG
BR 102 OF

PROJECT NO. F 021-1(8)S
SHEET NO. 14 OF 76