COMPOSITE SHEET - TRAFFIC SIGN SUMMARY - TRAFFIC ITEM SUMMARY - NOTES AND DETAILS

TRAFFIC SIGN SUMMARY

MILEMARKER, STATION OR SIGN NUMBER	LEGEND	TYPE	SIGN DIMENSIONS	EXISTING SIGNS TO BE SALVAGED: REMOVE (S.F.)	↓	RETAIN (X)	NEW AND SALVAGED SIGNS (S.F.): NEW "A"	SALVAGED "A"	NEW "B"	SALV. "B"	EXISTING POSTS: RETAIN	DRILL	SALV.	NEW POSTS: NUMBER OF POSTS	TYPE "A" (FLANGED CHANNEL): 2.0 LB./FT.	2.5 LB/FT.	3.0 LB/FT.	TYPE "C" (ALUMINUM): 3" ∅	3" □	4" ∅ MOD.	4" ∅	TYPE "B" BR'KAWAY STEEL	REMARKS	FOR SIGN DETAIL SEE SHEET OR STANDARD SHEET NUMBER
TOTALS	COLUMN																							
	PROJECT																							

TRAFFIC ITEM SUMMARY

ITEM NUMBER	ITEM	UNIT		SUB TOTAL		ROUNDING			TOTAL
646.35	TEMPORARY 4" REFLECTORIZED WHITE LINE	L.F.		1900		-			1900
646.36	TEMPORARY 4" REFLECTORIZED YELLOW LINE	L.F.		1840		-			1840
646.64	DURABLE 24" STOP BAR	L.F		26		-			26
646.66	DURABLE LETTER IN WORD MARKINGS	EA.		4		-			4
675.20	TRAFFIC SIGNS TYPE "A"	S.F.		56.5		0.5			57
675.35	TRAFFIC SIGN POSTS, TYPE "A"	LB.		350		-			350
675.53	REMOVING SIGNS	EA.		13		-			13

NOTES AND DETAILS

PAVEMENT MARKING NOTES-

TEMPORARY CENTERLINE MARKINGS SHALL BE APPLIED ON EACH PAVEMENT COURSE. EDGE LINES NEED ONLY BE APPLIED ON THE FINAL PAVEMENT COURSE.

SURVEYED BY _____ DATE _____
DRAWN BY _____ DATE _____
TRACED BY _____ DATE _____

HINESBURG

PROJ. F NO. 021-1(8)S

SHEET 21 OF 76

07