EARTHWORK SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

FED. ROAD DIVISION NO.	STATE	PROJECT NO.	FISCAL YEAR POST AID	SHEET NO.	TOTAL SHEETS
1	VT.				

V.C.	% GRADE	STATION	GRADES ELEVATION ON TANGENT	GRADES ELEVATION ON V CURVES	CORR V.C.	DIST.	TOTAL EXCAVATION EARTH AND ROCK AREA	TOTAL EXCAVATION EARTH AND ROCK CU. YDS.	SOLID ROCK EXCAVATION AREA	SOLID ROCK EXCAVATION CU. YDS.	EMBANKMENT AREA	EMBANKMENT CU. YDS.	BASE AREA	BASE CU. YDS.
400' VC	+0.0526 %	225+00	193.32	193.32	0	50	112		16					
								196		30				
		+50	193.34	193.32	-0.02		103		16		0			
								169		30		6		
		226	193.37	193.28	-0.09		82		16		6			
								154		30		87		
		+50	193.39	193.18	-0.21		81		16		85			
													C	1991
		+59	193.40	193.17	-0.23			148		30		111	F	235
													F.FAC	1.15
		227	193.42	193.05	-0.37		76		16		32			
								196		30		30	EXC	1721
		+50	193.08	192.87	-0.21		135		16		0			
								257		30			R	300
		228	192.74	192.65	-0.09		142		16					
								238		30				
		+50	192.40	192.38	-0.02		115		16					
								218		30				
	-0.6800 %	229	192.06	192.06	0		120		16					
		+39	191.79					219		30				
		+50	191.72				117		16		0			
								196		30		1		
		230	191.38	191.38	0		95		16		1			
								194		30		1		
200' VC		+50	191.04	191.08	+0.04		115		16		0		C	803
								209		30			F	7
		231	190.70	190.87	+0.17		111		16		0		F.FAC	1.15
								205		30		3		
		+50	190.70	190.74	+0.04		110		16		3		EXC	795
	0.0000 %	232	190.70	190.70	0	50		195		30		3		
							101		16		0		R	120
		+50			232+00	END APPROACH CONSTRUCTION								
		233												
							NOTE: ROCK IS NOT PAYCREDIT BECAUSE IT IS EXISTING CONCRETE PAVEMENT.							
		CARRIED FORWARD												
		COLUMN FOOTINGS						2794		420		242		

V.C.	% GRADE	STATION	GRADES ELEVATION ON TANGENT	GRADES ELEVATION ON V CURVES	CORR V.C.	DIST.	TOTAL EXCAVATION EARTH AND ROCK AREA	TOTAL EXCAVATION EARTH AND ROCK CU. YDS.	AREA	CU. YDS.	EMBANKMENT AREA	EMBANKMENT CU. YDS.	BASE AREA	BASE CU.YDS.
CARRIED FORWARD														
COLUMN FOOTINGS														

V.C.	% GRADE	STATION	GRADES ELEVATION ON TANGENT	GRADES ELEVATION ON V. CURVES	CORR V.C.	DIST.	TOTAL EXCAVATION EARTH AND ROCK AREA	TOTAL EXCAVATION EARTH AND ROCK CU. YDS.	AREA	CU. YDS.	EMBANKMENT AREA	EMBANKMENT CU. YDS.	BASE AREA	BASE CU. YDS.
CARRIED FORWARD														
COLUMN FOOTINGS														

PROJECT FERRISBURG

PROJECT F EGCF NO. 019-4 (11)

SHEET 7 OF 62 SHEETS

BRUNING 40-105 40592