

QUANTITY SHEET WEST RUTLAND-RUTLAND F020-1(10) C-2

APPROXIMATE SUMMARY OF QUANTITIES

DETAILED SUMMARY OF ITEMS

TEMPORARY EROSION CONTROL	EROSION CONTROL	R.O.W.	UTILITES	BRIDGE OVER DORR DRIVE	BRIDGE OVER OTTER CREEK	RAILROAD	WETLANDS	ROADWAY	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	QUANTITY	UNIT	ITEMS
								1	1	LS	CLEARING AND GRUBBING, PLUS INDIVIDUAL TREES AND STUMPS	201.10				CLEARING AND GRUBBING ITEM 201.10
																NOTE: ITEM 201.10 SHALL INCLUDE THE REMOVAL OF RAILROAD RUBBISH AT APPROXIMATE STATION 973+00#
							57500	1,185,000	1,242,500	CY	COMMON EXCAVATION	203.15				COMMON EXCAVATION ITEM 203.15
								10,000	10,000	CY	SOLID ROCK EXCAVATION	203.16	EST			
								25,000	25,000	CY	MUCK EXCAVATION	203.20	654	1,152,941	CY	MAINLINE ROADWAY
														6,638	CY	RAMPS
														1,774	CY	DORR DRIVE
					550			11,950	12,500	CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27	136	20,035	CY	EXCAVATION FROM SAND UNDER CUT AREAS
														36.12	CY	ROUNDING
														1,185,000	CY	TOTAL
								20,500	20,500	CY	SAND BORROW	203.31	65			
				24740	4,890			83,170	112,800	CY	GRANULAR BORROW	203.32	173			TRENCH EXCAVATION OF EARTH ITEM 204.20
								105,000	105,000	CY	ROCK BORROW	203.33				
								3350	3350	SY	FINE GRADING - SUBGRADE	203.40		12,262	CY	DRAINAGE
								20,950	21,400	CY	TRENCH EXCAVATION OF EARTH	204.20	85	8,243	CY	DESIGNED UNDERDRAIN
														360	CY	EST. UNDERDRAIN
														85	CY	ROUNDING
25		425												21,400	CY	TOTAL
								2000	2000	CY	TRENCH EXCAVATION OF ROCK	204.21	EST			
				480				2,120	2,600	CY	STRUCTURE EXCAVATION	204.25	44			GRANULAR BORROW ITEM 203.32
					1780			1,320	3,100	CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	38	27,404	CY	EST 12" TO CAP FILLS
														55,193	CY	DESIGNED IN BRIDGE AREAS
														400	CY	EST. FOR DRAINAGE
														173	CY	ROUNDING
								2,000	2,000	SY	DRILLING AND BLASTING OF SOLID ROCK SUBGRADE	206.10	EST	83,170	CY	TOTAL
								1700	1700	CY	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.26	41			
								330	330	TON	PLANT MIXED BASE COURSE	303.25	4			
								290	290	TON	BITUMINOUS CONCRETE PAVEMENT	406.25	16			
				652	910				1562	CY	CONCRETE, CLASS A	501.20				
				1393	1453			164	3,010	CY	CONCRETE, CLASS B	501.25	1.8			
				0.5	0.5				1	LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10				