

QUANTITY SHEET WEST RUTLAND-RUTLAND FO20-1(10) C-2

APPROXIMATE SUMMARY OF QUANTITIES

DETAILED SUMMARY OF ITEMS

TEMPORARY EROSION CONTROL	EROSION CONTROL	R. O. W.	UTILITIES	BRIDGE OVER DORR DRIVE	BRIDGE OVER OTTER CREEK	RAILROAD	WETLANDS	ROADWAY	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	QUANTITY	UNIT	ITEMS
				5162					5162	LF	STEEL PILING (HP 12X53)	505.15				
					15880				15880	LF	STEEL PILING (HP 14X89)	505.18				
				4	2				6	EA	PILE LOADING TESTS	505.40				
				453,250	1,254,760				1,708,010	LB	STRUCTURAL STEEL (PLATE GIRDER)	506.91				
					24				24	EA	BEARING DEVICE ASSEMBLY (AT STATION 943+20 & 946+80)	506.99				
					24				24	EA	BEARING DEVICE ASSEMBLY (AT STATION 944+20 & 945+80)	506.99				
				10					10	EA	BEARING DEVICE ASSEMBLY (AT STATION MB930+41 & EB930+24)	506.99				
				20					20	EA	BEARING DEVICE ASSEMBLY (AT STATION MB 929+60, 932+03, EB 930+34 AND 932+37)	506.99				
				10					10	EA	BEARING DEVICE ASSEMBLY (AT STATION MB 931+39 AND EB 931+87)	506.99				
				341,160	440,880			11,360	793,400	LB	REINFORCING STEEL	507.15	19			
					1				1	LS	SHEAR CONNECTORS AT OTTER CREEK	508.15				
				1					1	LS	SHEAR CONNECTORS AT DORR DRIVE	508.15				
				106	108				214	GAL	WATER REPELLENT	514.10				
				90	164				254	LF	FLAS-TO-MERIC EXPANSION DAM (3" MOVEMENT)	516.33				
					1				1	LS	COFFERDAM (AT STATION EB 944+20)	530.10				
					1				1	LS	COFFERDAM (AT STATION EB 945+80)	530.10				
					1				1	LS	COFFERDAM (AT STATION MB 944+20)	530.10				
					1				1	LS	COFFERDAM (AT STATION MB 945+80)	530.10				
								2,786	2,786	LF	18" ACCGMP .064	601.1552				
								536	536	LF	18" ACCGMP .079	601.1553				
								252	252	LF	24" ACCGMP .064	601.1572				
								200	200	LF	36" ACCGMP .079	601.1593				
								262	262	LF	42" ACCGMP .109	601.1604				
								602	602	LF	60" ACCGMP .138	601.1635				
								72	72	LF	60" ACCGMP .168	601.1636				
								1926	1926	LF	18" RCP CL III	601.2623				
								1348	1,348	LF	24" RCP CL III	601.2643				
								300	300	LF	30" RCP CL III	601.2653				
								300	300	LF	36" RCP CL III	601.2663				
								100	100	LF	36" RCP CL V	601.2665				
								460	460	LF	42" RCP CL III	601.2673				
								350	350	LF	48" RCP CL III	601.2683				
								6	6	EA	18" ACCGMP ELBOW	601.5552				
								3	3	EA	24" ACCGMP ELBOW	601.5572				
								2	2	EA	36" ACCGMP ELBOW	601.5593				
								8	8	EA	18" MES FOR 18" ACCGMP	601.6222				