QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			NON-GOV'T PARTICIPATION	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						14	14	EA	BOUNDARY MARKERS	619.10	
						27	27	EA	STEEL MARKER POSTS	619.16	
						2	2	EA	REMOVING & RESETTING PROPERTY MARKERS	619.20	EST
						655	655	L.F.	CHAIN-LINK FENCE, 6 FEET	620.12	
						28	28	L.F.	GATE FOR CHAIN-LINK FENCE, 6 FEET (DOUBLE CANTILEVER SLIDE)	620.16	2
						7	7	EA	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21	
						440	440	L.F.	REMOVAL OF EXISTING FENCE	620.55	
						3,350	3,350	L.F.	SNOW FENCE (MODIFIED)	620.70	
						1,190	1,190	L.F.	STEEL BEAM GUARDRAIL (WITH STEEL POSTS)	621.20	2.50
						4	4	EA	MODIFIED ECCENTRIC LOADER TERMINAL	621.52	
						100	100	L.F.	ALUMINUM APPROACH RAILING	621.74	
						810	810	L.F.	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	8
					5		5	EA.	SETTLEMENT PLATFORM TYPE I	623.21	
					3		3	EA.	SETTLEMENT PLATFORM, VIBRATING WIRE	623.23	
						580	580	HR.	UNIFORM TRAFFIC OFFICER	630.10	
						1,200	1,200	HR.	FLAGGERS	630.15	
						1	1	L.S.	FIELD OFFICE - ENGINEERS	631.10	
					1		1	L.S.	TESTING EQUIPMENT - CONCRETE	631.16	
						1	1	L.S.	TESTING EQUIPMENT - BITUMINOUS	631.17	
					1		1	L.S.	TESTING EQUIPMENT - PROTECTIVE COATING	631.18	
						1	1	EA	FIELD OFFICE TELEPHONE (NOT A BID ITEM)	631.25	
				1040			1040	HR.	EMPLOYEE TRAINEESHIP	634.10	
						1	1	L.S.	MOBILIZATION	635.10	
						190	190	L.F.	PAINTED CURB (YELLOW)	646.27	3
						4,740	4,740	L.F.	DURABLE 4" WHITE LINE	646.40	4
						5,110	5,110	L.F.	DURABLE 4" YELLOW LINE	646.41	8
						320	320	L.F.	DURABLE 8" YELLOW LINE	646.43	
						54	54	L.F.	DURABLE 24" STOP BAR	646.46	
						14	14	EA	DURABLE LETTER OR SYMBOL	646.50	
						2,600	2,600	L.F.	TEMPORARY 4" WHITE LINE	646.60	EST
						2,200	2,200	L.F.	TEMPORARY 4" YELLOW LINE	646.61	EST
						24	24	L.F.	TEMPORARY 24" STOP BAR	646.66	EST
						20	20	EA	LINE STRIPING TARGETS	646.73	2
						1,700	1,700	S.Y.	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR	649.11	32
					1,890		1,890	S.Y.	GEOTEXTILE UNDER STONE FILL	649.31	
						650	650	S.Y.	GEOTEXTILE FABRIC FOR SILT FENCE	649.51	EST
						140	140	LB	SEED	651.15	7
						1	1	LB	SEED (MOD.#1) (AGROSTIS ALBA) (REDTOP)	651.15	0.2

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATE OF VERMONT
AGENCY OF TRANSPORTATION

Town Of SPRINGFIELD	Bridge No. 44
Highway No. U.S. ROUTE 5	Log Sta. Surv. Sta.
U.S. ROUTE 5 OVER BLACK RIVER	
SUMMARY OF QUANTITIES	
Designed By JRW	Drawn By RR/CJM
Checked By Date	Bridge Design Supervisor P. PIERCE Date
PROJECT SPRINGFIELD	PROJECT NO. BRS-RS 0113 (8)
I.G.C. Info. /usr5/j9145622/quant2.dgn	
Bridge Sheet No.	Sheet 6 of 90

23-MAY-1996 13:52