QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			NON-GOV'T PARTICIPATION	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						3	3	LB	SEED (MOD.#2)	651.15	0.2
									(PHALARIS ARUNDINACEA) (REED CANARY GRASS)		
						6	6	LB	SEED (MOD.#3)	651.15	0.4
									(FESTUCA ARUNDINACEA) (KENTUCKY FESCUE)		
						9	9	LB	SEED (MOD.#4) (LOLIUM PERRENE) (RYEGRASS)	651.15	0.6
						15	15	LB	SEED, WINTER RYE	651.17	EST
						1,125	1,125	LB	FERTILIZER	651.18	20
						5	5	TON	AGRICULTURAL LIMESTONE	651.20	0.6
						6	6	TON	HAY MULCH	651.25	0.6
						350	350	EA	HAY BALES FOR EROSION CONTROL	651.26	EST
						600	600	C.Y.	TOPSOIL	651.35	6
					1,330	3,245	4,575	S.Y.	GRUBBING MATERIAL	651.40	28
						240	240	S.Y.	EROSION MATTING	654.10	8
						20	20	EA	DECIDUOUS SHRUBS (SAMBUCUS CANDENSIS) (ELDERBERRY)	656.35	
									(24 INCH HEIGHT, CONTAINER)		
						31	31	EA	DECIDUOUS SHRUBS (CORNUS AMOMUM) (SILKY DOGWOOD)	656.35	
									(24 INCH HEIGHT, CONTAINER)		
						41	41	EA	DECIDUOUS SHRUBS (CORNUS SERICEA) (RED OSIER DOGWOOD)	656.35	
									(24 INCH HEIGHT, CONTAINER)		
						39	39	EA	DECIDUOUS SHRUBS (CORNUS RACEMOSA) (GRAYSTEM DOGWOOD)	656.35	
									(24 INCH HEIGHT, CONTAINER)		
						840	840	EA	GROUND COVER AND VINES	656.40	4
									(LEERSIA ORYZOIDES) (RICE CUTGRASS) (BARE ROOT)		
						540	540	EA	GROUND COVER AND VINES	656.40	2
									(SCIRPUS CYPERINUS) (WOOL GRASS) (BARE ROOT)		
						30	30	EA	GROUND COVER AND VINES	656.40	3
									(ONOCLEA SENSIBILIS) (SENSITIVE FERN) (BARE ROOT)		
						99	99	S.F.	TRAFFIC SIGNS, TYPE 'A'	675.20	0.17
						846	846	LB	FLANGED CHANNEL SIGN POSTS	675.30	
						854	854	LB	TUBULAR STEEL SIGN POSTS	675.33	
						8	8	EA	FOUNDATION FOR TUBULAR STEEL POSTS	675.43	
						65	65	EA	REMOVING SIGNS	675.50	
						31	31	EA	ERECTING SALVAGED SIGNS	675.60	
			16				16	S.F.	TRAVEL INFORMATION SIGNS (MODIFIED)	680.20	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

Revised 7/9/96

STATE OF VERMONT
AGENCY OF TRANSPORTATION

Town Of SPRINGFIELD	Bridge No. 44
	Log Sta.
Highway No. U.S. ROUTE 5	Surv. Sta.
U.S. ROUTE 5 OVER BLACK RIVER	
SUMMARY OF QUANTITIES	
Designed By JRM	Drawn By RR/CJM
Checked By RAL Date 3/95	Bridge Design Supervisor P. PIERCE Date
PROJECT SPRINGFIELD	PROJECT NO. BRS-AS 0113 (8)
I.G.C. Info. /usr5/J9145822/quant3.dgn	
Bridge Sheet No.	Sheet 7 of 90

23-MAY-1996 13:52