



ANCHOR BOLT NOTE:
ALL ANCHOR BOLTS FOR BEARING DEVICES TO BE CAST IN PLACE DURING CONCRETE CAP POUR.

- NOTES:**
- 3" CLEAR COVER IN FOOTING UNLESS OTHERWISE NOTED.
 - 4" CLEAR COVER ON ALL EXPOSED FACES IN STEM AND CAP.
 - E.F. - DENOTES EACH FACE.
 - ▲ - DENOTES CUT TO FIT IN FIELD.
 - I - DENOTES VERTICAL HP 12 X 74 PILE.
 - ▽ - DENOTES 1 ON 4 BATTERED HP 12 X 74 PILE.

STATE OF VERMONT AGENCY OF TRANSPORTATION	
Town Of SPRINGFIELD	Bridge No. 44
Highway No. U.S. ROUTE 5	Log Sta.
U.S. ROUTE 5 OVER BLACK RIVER	
PIER DETAILS	
Designed By S. BAKI	Drawn By W. GAYNOR
Checked By S. BAKI	Bridge Design Supervisor P. PIERCE Date 5/96
PROJECT SPRINGFIELD	PROJECT NO. BRS-RS 0113 (8)
L.G.C. Info. cr:\usr\j945622\spierpln.dgn	
Bridge Sheet No. BR127	Sheet 56 of 90