

# QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES														TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES					
						Deck	Abutment 1	Abutment 2	Approach Slab 1	Approach Slab 2	Channel	Roadway	Erosion	Temp Erosion	E & C Items	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS	
														2			EST	2		T	HAY MULCH	651.25			
														25			EST	25		EACH	HAY BALES FOR EROSION CONTROL	651.26			
													990			EST	990		CM	TOPSOIL	651.35				
										650							650		SM	GRUBBING MATERIAL	651.40				
												2					2		EACH	EVERGREEN TREES (PICEA GLAUCA, B&B, 3.5 m HT.)	656.20				
												2					2		SM	TRAFFIC SIGNS, TYPE A	675.20				
																				<b>BEGIN OPTION POSTS</b>					
												7					7		M	FLANGED CHANNEL SIGN POST	675.301				
												7					7		M	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341				
																				<b>END OPTION POSTS</b>					
												13					13		EACH	REMOVING SIGNS	675.50				
						4	2	1									7		EACH	JUNCTION BOX	678.26				
						4	1	1									6		EACH	LIGHT POLE BASE	679.21				
												1					1		EACH	POWER STANCHION (MOD)	679.28				
						4	1	1									6		EACH	LIGHT POLE	679.45				
						4	1	1									6		EACH	LUMINAIRE	679.50				