STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET

Metric

CURB

BEGIN STATION	END STATION	POSITION		REMARKS
		LEFT	RIGHT	
km + m	km + m	m	m	
1+159.3	1+173.6	14.3		
1+191.0	1+219.2	28.2		
1+193.8	1+246.9		53.1	
1+244.0	1+252.1	8.1		
1+301.1	1+310.8		9.7	
1+315.3	1+384.0	68.7		
1+330.9	1+399.0		68.1	
		---------	---------	
	TOTAL	119.3 +	130.9 =	250.2 m

SIDEWALK

BEGIN STATION	END STATION	POSITION		REMARKS
		LEFT	RIGHT	
km + m	km + m	m^2	m^2	

APPROACH RAILING

BEGIN STATION	END STATION	POSITION		END TREATMENT	
		LEFT	RIGHT	BEGIN	END
km + m	km + m	m	m	ea	ea
1+192.2	1+246.9		55.5		
1+247.2	1+252.1	11.4			
1+301.1	1+312.4		13.6		
1+315.3	1+342.7	27.6			
		---------	---------		
	TOTAL	39.0 +	69.1 =	108.1 m	

UNDERDRAIN

BEGIN STATION	END STATION	TYPE	POSITION	DIA.	LENGTH	TRENCH		GRAN BKFILL	FB	MKR PST
						EARTH	ROCK			
km + m	km + m			mm	m	m^3	m^3	m^3	ea	ea
1+191.9	1+250.0	U	LEFT	150	60	67.5			1	1
1+200.0	1+240.0	U	RIGHT	150	40	55.0			1	1
1+254.3		U	CL	150	20	0			1	1
1+299.7		U	CL	150	28	0			1	1
1+316.3	1+379.0	U	LEFT	150	63	20.8			1	1
1+331.8	1+359.0	U	RIGHT	150	29	28.6			1	1
1+360.3	1+400.0	U	RIGHT	150	40	37.2			1	1
1+380.3	1+400.0	U	LEFT	150	20	15.9			1	1
TOTAL	UNDERDRAIN			150	300	225.0			8	8
1+240.0	1+251.5	C	RIGHT	150	12	6.3				1
TOTAL	CARRIER PIPE			150	12	6.3				1

PROJECT NAME: **BRISTOL**
PROJECT NUMBER: **ER 021-1(13)**

FILE NAME: **/str2/78f188/df188de.xls**
PROJECT LEADER: **PORTALUPI**
DESIGNED BY: **STR2**
ITEM DETAIL SHEET #1

PLOT DATE: **6/28/99**
DRAWN BY: **WEEBER**
CHECKED BY: **0**
SHEET **8** OF **67**