STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	108+34 RT	A	VD-700	6	10		0020 1204 0020	0.42								1		9											E-138
EB	108+80 RT	A	D17-2	42	42		TRUCK LANE ¼ MILE	12.25								1		17									X		
EB	117+50 RT	A	W2-2R	30	30			6.25								1		17									X		
WB	118+90 LT	F	VD-700	6	10		0020 1204 0040	0.42								1		8											E-138
EB	124+22 RT	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		17											E-141
EB	124+64 RT	A/B	D3-1	36	12		Porter Rd	3.00																		MOUNTED ABOVE R1-1 (ON THE SAME POST)		68	
EB	124+64 RT	D	R1-1	30	30		STOP	6.25								1		16									X		
EB	125+00 RT	A	R4-3	24	30		SLOWER TRAFFIC KEEP RIGHT	5.00								1		16									X		
EB	129+46 RT	A	VD-700	6	10		0020 1204 0060	0.42								1		10											E-138
WB	140+02 LT	F	VD-700	6	10		0020 1204 0080	0.42								1		8											E-138
EB	150+58 RT	A	VD-700	6	10		0020 1204 0100	0.42								1		8											E-138
EB	152+00 RT	A	W9-1	36	36		RIGHT LANE ENDS	9.00								2		36									X		
WB	156+00 LT	F	W7-1a	30	30		8%	6.25								2		28									X		
EB	156+50 RT	A	W4-2R	36	36			9.00								2		28									X		
EB	160+00 RT	A	VR-023b	24	30		$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	5.00								1		12											E-144
WB	161+14 LT	F	VD-700	6	10		0020 1204 0120	0.42								1		8											E-138
										EA	EA	EA	EA	EA	EA		FT	FT 238	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 69.52	SF	EA				EA		EA 18	FT 238			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: CABOT-DANVILLE
PROJECT NUMBER: FEGC F 028-3(26) C/1

FILE NAME: d78d058frm.dgn
PROJECT LEADER: K. ROBIE
DESIGNED BY: I. SHEA
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 13-OCT-2010
DRAWN BY: I. SHEA
CHECKED BY: S. MENARD
SHEET 67 OF 250