

MITIGATION QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES							SUMMARY OF ESTIMATED QUANTITIES							SUMMARY OF ESTIMATED QUANTITIES							
MITIGATION SITE COMMON ITEMS	MITIGATION SITE ALTRNATE ZAI	MITIGATION SITE ALTRNATE ZA2	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	MITIGATION SITE COMMON ITEMS	MITIGATION SITE ALTRNATE ZAI	MITIGATION SITE ALTRNATE ZA2	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	MITIGATION SITE COMMON ITEMS	MITIGATION SITE ALTRNATE ZAI	MITIGATION SITE ALTRNATE ZA2	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	
1			1	LS	CLEARING AND GRUBBING (INCLUDING INDIVIDUAL TREES AND STUMPS) (MITIGATION SITE)	201.10															
74,158			74,158	CY	COMMON EXCAVATION	203.15	10			10	EA	EVERGREEN TREES (LARIX LARICINA) (5'-6' HT.) (CONT.)	656.20		8,550		8,550	CY	BEGIN ALTERNATE ZAI (TOPSOIL)		
500			500	CY	SOLID ROCK EXCAVATION	203.16															651.35
110			110	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35															
42			42	CY	AGGREGATE SURFACE COURSE	401.10	23			23	EA	DECIDUOUS TREES (ACER RUBRUM) (5'-6' HT.) (CONT.)	656.30								
20			20	HR	BULLDOZER RENTAL, TYPE I	608.10	21			21	EA	DECIDUOUS TREES (FRAXINUS PENNSYLVANICA) (5'-6' HT.) (CONT.)	656.30								
20			20	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	11			11	EA	DECIDUOUS TREES (POPULUS DELTOIDES) (5'-6' HT.) (CONT.)	656.30								
20			20	HR	LOADER RENTAL, TYPE I	608.40															
10			10	MGAL	DUST CONTROL WITH WATER	609.10	20			20	EA	DECIDUOUS SHRUBS (CORNUS SERICEA) (3'-4' HT.) (CONT.)	656.35								
476			476	LF	CHAIN LINK FENCE, 6 FEET	620.12	42			42	EA	DECIDUOUS SHRUBS (ILEX VERTICILLATA) (3'-4' HT.) (CONT.)	656.35								
24			24	LF	GATE FOR CHAIN LINK FENCE, 6'	620.16	160			160	EA	DECIDUOUS SHRUBS (VIBURNUM RECOGNITUM) (3'-4' HT.) (CONT.)	656.35								
4			4	EA	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21	123			123	EA	DECIDUOUS SHRUBS (CRATAEGUS CRUS-GALLI) (3'-4' HT.) (CONT.)	656.35								
30			30	LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95															
200			200	HR	FLAGGERS	630.15	47			47	CY	LANDSCAPE BACKFILL, TRUCK MEASUREMENT	656.80								
1			1	LS	MOBILIZATION (MITIGATION SITE)	635.11	18			18	SF	TRAFFIC SIGN, TYPE A	675.20								
1			1	LS	TRAFFIC CONTROL (MITIGATION SITE)	641.10	90			90	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341								
1,000			1,000	SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	2,420			2,420	CY	SPECIAL PROVISION (HYDRIC SOIL)	900.608								
540			540	SY	GEOTEXTILE FOR SILT FENCE WOVEN WIRE REINFORCED	649.515	2			2	EA	SPECIAL PROVISION (CUT HABITAT TREE)	900.620								
132			132	LB	SEED	651.15	1			1	EA	SPECIAL PROVISION (MONITORING GAUGE BOULDER)	900.620								
78			78	LB	SEED, WINTER RYE	651.17	8			8	EA	SPECIAL PROVISION (BLUEBIRD BOX AND POST)	900.620								
4420			4420	LB	FERTILIZER	651.18	4			4	EA	SPECIAL PROVISION (WOOD DUCK BOX AND POST)	900.620								
18			18	TON	AGRICULTURAL LIMESTONE	651.20	26			26	EA	SPECIAL PROVISION (VAST SIGN CEDAR POSTS)	900.620								
4			4	TON	HAY MULCH	651.25	6			6	LB	SPECIAL PROVISION (WILD RICE SEED)	900.635								
15			15	TON	STRAW MULCH	651.29	247			247	LB	SPECIAL PROVISION (EROSION CONTROL/RESTORATION MIX)	900.635								
1			1	LS	EPSC PLAN (MITIGATION SITE)	652.10	1,720			1,720	SY	SPECIAL PROVISION (LANDSCAPE FABRIC)	900.675								
96			96	HR	MONITORING EPSC PLAN (MITIGATION SITE)	652.20															
1			1	LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (MITIGATION SITE)	652.30															
680			680	SY	TEMPORARY EROSION MATTING	653.20															
240			240	CY	VEHICLE TRACKING PAD	653.35															
4,510			4,510	LF	BARRIER FENCE	653.50															
6,260			6,260	LF	PROJECT DEMARCATION FENCE	653.55															
110			110	LF	LIVE FASCINE	653.65															

PROJECT NAME: CABOT-DANVILLE
PROJECT NUMBER: FECC F 028-3(26)

FILE NAME: xd079qs.dgn PLOT DATE: 11/16/2010
PROJECT LEADER: C.W. BRODIE DRAWN BY: E.B. SMALL
DESIGNED BY: C.W. BRODIE CHECKED BY: J.K. BENSON
MITIGATION QUANTITY SHEET SHEET 197 OF 250