STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET 2

CURB

BEGIN STATION	END STATION	POSITION		REMARKS
		LEFT FT	RIGHT FT	

NESTED GUARDRAIL

BEGIN STATION	END STATION	POSITION		REMARKS
		LEFT FT	RIGHT FT	

GUARDRAIL

BEGIN STATION	END STATION	POSITION		END TREATMENT	
		LEFT FT	RIGHT FT	BEGIN EA	END EA

UNDERDRAIN

BEGIN STATION	END STATION	TYPE	POSITION	DIA. IN	LENGTH FT	TRENCH EARTH CY	TRENCH ROCK CY	BACKFILL CY	FB EA	MKR PST EA	PIPE NO.
80+00	84+75	U	RT	8	475	204.7	10	205.3	1	1	U26
80+00	84+75	U	LT	8	475	182.9	9	205.3	1	1	U27
84+80	88+91	U	RT	8	411	178.3	9	177.6	1	1	U28
84+80	88+82	U	LT	8	402	174.5	9	173.8	1	1	U29
88+82	88+98	C	LT	8	24	6.9	0	10.4		1	C16
88+91	88+98	C	RT	8	11	3.8	0	4.8		1	C17
89+20	91+23	U	RT	8	203	80.3	4	87.7	1	1	U30
89+20	91+25	U	LT	8	205	68.6	3	86.6	1	1	U31
91+23	91+32	C	RT	8	18	6.8	0	7.8		1	C18
91+25	91+38	C	LT	8	25	7.3	0	10.8		1	C19
94+50	100+00	U	RT	8	550	239.5	12	237.7	1	1	U32
95+00	100+00	U	LT	8	500	239.5	12	216.1	1	1	U33
100+00	104+50	U	RT	8	450	198.8	10	194.5	1	1	U34
100+00	104+50	U	LT	8	450	176.7	9	194.5	1	1	U35
104+50	104+75	C	RT	8	32	7.1	0	13.8		1	C20
104+50	104+78	C	LT	8	35	7.7	0	15.1		1	C21
104+95	105+25	C	RT	8	35	7.7	0	15.1		1	C22
104+95	105+25	C	LT	8	35	7.7	0	15.1		1	C23
105+25	111+50	U	RT	8	625	276.2	14	270.1	1	1	U36
105+25	111+50	U	LT	8	625	276.2	14	270.1	1	1	U37
111+50	118+50	U	RT	8	700	308.6	15	302.6	1	1	U38
111+50	118+00	U	LT	8	650	263.1	13	280.9	1	1	U39
118+50	118+75	C	LT	8	26	10.8	1	11.2		1	C24
118+75	124+00	U	LT	8	525	232.2	12	226.9	1	1	U40
119+25	124+00	U	RT	8	475	230.3	12	205.3	1	1	U41
119+25	119+25	C	RT	8	8	2.5	0	3.5		1	C25
124+00	129+00	U	RT	8	500	198.8	10	216.1	1	1	U42
124+00	128+00	U	LT	8	400	176.8	9	172.9	1	1	U43
129+00	134+50	U	RT	8	550	242.5	12	237.7	1	1	U44
135+00	139+50	U	RT	8	450	198.8	10	194.5	1	1	U45
135+00	140+75	U	LT	8	575	260.3	13	248.5	1	1	U46
139+50	145+00	U	RT	8	550	242.5	12	237.7	1	1	U47
140+75	140+75	C	LT	8	27	6.2	0	11.7		1	C26
145+00	149+25	U	RT	8	425	187.7	9	194.5	1	1	U48
146+00	149+57	U	LT	8	350	154.8	8	151.3	1	1	U49
149+25	149+50	C	RT	8	56	8.8	0	17.3		1	C27
149+50	149+50	C	LT	8	18	4	0	7.8		1	C28
153+00	156+25	U	LT	8	325	142.3	7	140.5	1	1	U50
153+00	153+00	C	LT	8	40	9.9	0	17.3		1	C29
165+55	156+75	C	LT	8	27	4.5	0	11.7		1	C30

LEGEND
U = UNDERDRAIN
C = CARRIER PIPE

PROJECT NAME: CHARLOTTE
PROJECT NUMBER: F EGC 019-4(20)

FILE NAME: d78d062_frm.dgn
PROJECT LEADER: K. UPMAL
DESIGNED BY: B. KIPP
ITEM DETAIL SHEET 2

PLOT DATE: 15-MAR-2016
DRAWN BY: A. AGRAWAL
CHECKED BY: C. LEACH
SHEET 24 OF 499