STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET 3

CURB

BEGIN STATION	END STATION	POSITION		REMARKS
		LEFT FT	RIGHT FT	

NESTED GUARDRAIL

BEGIN STATION	END STATION	POSITION		REMARKS
		LEFT FT	RIGHT FT	

GUARDRAIL

BEGIN STATION	END STATION	POSITION		END TREATMENT	
		LEFT FT	RIGHT FT	BEGIN EA	END EA

UNDERDRAIN

BEGIN STATION	END STATION	TYPE	POSITION	DIA.	LENGTH	TRENCH		BACKFILL	FB	MKR PST	PIPE NO.
						EARTH	ROCK				
				IN	FT	CY	CY	CY	EA	EA	
156+75	158+50	U	LT	8	175	25	1	32.4	1	1	U51
157+50	160+68	U	RT	8	318	122.8	6	138.3	1	1	U52
158+50	160+68	U	LT	8	218	102.6	5	137.4	1	1	U53
160+68	160+81	C	RT	8	20	4.4	0	8.6		1	C31
160+68	160+68	C	LT	8	32	6.5	0	13.8		1	C32
160+93	160+93	C	LT	8	41	4.4	0	17.7		1	C33
160+93	163+00	U	LT	8	207	87	4	89.5	1	1	U55
UNDERDRAIN TOTALS:					25056	10851	536	10850	57	57	
CARRIER PIPE TOTALS					1016	216	1	419		34	
TOTALS						11067	537	11269	57	91	

LEGEND
U = UNDERDRAIN
C = CARRIER PIPE

PROJECT NAME: CHARLOTTE
PROJECT NUMBER: F EGC 019-4(20)

FILE NAME: d78d062_frm.dgn
PROJECT LEADER: K. UPMAL
DESIGNED BY: B. KIPP
ITEM DETAIL SHEET 3

PLOT DATE: 15-MAR-2016
DRAWN BY: A. AGRAWAL
CHECKED BY: C. LEACH
SHEET 25 OF 499