STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																										
STA 104+32 RT	0070 0404 0180	1	6	10	0.42						1				8.0			X																	VD-700			T-44
STA 104+77 RT	BRIDGE 142 US7	1	6	10	0.42						1				8.0			X																	VD-701			T-42
STA 104+93 LT	BRIDGE 142 US7	1	6	10	0.42						1				8.0			X																	VD-701			T-42
STA 105+36 LT	SPEED LIMIT 50	1	24	30	5.00						1					9.5		X																		R2-1		
STA 108+76 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					9.5		X																	VR-017			E-141
STA 109+14 RT	Higbee Rd STOP 0070 0404 0189	2 1 1	42 30 6	12 30 10	3.50 6.25 0.42						1					10.5		X																	STREET SIGN BACK TO BACK VD-700	R1-1	226	T-44
STA 114+89 LT	0070 0404 0200	1	6	10	0.42						1				8.0			X																	VD-700			T-44
STA 125+45 RT	0070 0404 0220	1	6	10	0.42						1				8.0			X																	VD-700			T-44
STA 129+77 RT	44 22 88 57	1					X			X																								REMOVE, SALVAGE AND RESET ADDRESS POST			
STA 131+98 LT	Wildwood West Pvt	1 1	60 60	12 12	5.00 5.00						2					16.0		X																	BACK TO BACK		226	
STA 136+00 LT	0070 0404 0240	1	6	10	0.42						1				8.0			X																	VD-700			T-44
STA 142+15 RT	Ridge Road Pvt	1 1	54 54	12 12	4.50 4.50						2					16.0		X																	BACK TO BACK		226	
STA 146+56 RT	0070 0404 0260	1	6	10	0.42						1				8.0			X																	VD-700			T-44
STA 150+99 RT	Mt. Carmel Catholic Church rt. to Spear St Congregational Church, UCC							X X			2					30.0		X																	NON PARTICIPATING			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VAOT DIVISION'S "SIGN POST DESIGN GUIDELINE."

SEE SPECIAL PROVISIONS FOR ADDITIONAL SIGN INFORMATION

FT FT FT FT FT FT EA LB LB LB LB LB LB LB LB

56.0 91.5

SHEET TOTALS	SF 42.11	SF 0.00	EA. 1	EA 2	FT 0.00	FT 147.5	LB 0.00	EA. 0	LB 0.00	EA. 0	EA. 0	LB 0

TRAFFIC SIGN SUMMARY SHEET 4

PROJECT NAME: CHARLOTTE
PROJECT NUMBER: F EGC 019-4(20)

FILE NAME: d78d062_frm.dgn
PROJECT LEADER: K. UPMAL
DESIGNED BY: B.KIPP
TRAFFIC SIGN SUMMARY SHEET 4

PLOT DATE: 15-MAR-2016
DRAWN BY: B.KIPP
CHECKED BY: C. LEACH
SHEET 224 OF 499