STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #5

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																										
STA 153+68 RT	Colonel Williams Way Pvt	1 1	72 72	12 12	6.00 6.00						2					16.0		X																	BACK TO BACK		226	
STA 157+12 LT	0070 0404 0280	1	6	10	0.42						1				8.0			X																VD-700			T-44
STA 157+93 LT	R	1	24	24	4.00						1					9.0		X																	R8-3		
STA 157+94 RT	R BEGIN	1	24 24	24 12	4.00 2.00						1					10.0		X																	R8-3 M4-14		
STA 159+94 RT	Travel Information at wildflower farm							X X			2					30.0		X																NON PARTICIPATING			E-125
STA 160+95 LT	SPEED LIMIT 50	1	24	30	5.00						1					9.5		X																	R2-1		
STA 162+65 RT	FERRY TO NY STATE TURN LEFT ½ MILE						X				2					20.0		X																			
STA 162+93 LT	R	1	24	24	4.00						1					9.0		X																	R8-3		
STA 164+37 LT	R	1	24	24	4.00						1					9.0		X																	R8-3		
STA 164+44 RT	R	1	24	24	4.00						1					9.0		X																	R8-3		
	SUBTOTAL THIS SHEET				39.42		1	2							8.0	121.5																					
	SUBTOTAL SHEET 221				54.70		2	0							56.0	93.0																					
	SUBTOTAL SHEET 222				78.68		0	5							8.0	178.5																					
	SUBTOTAL SHEET 223				36.68		0	0							57.5	44.5																					
	SUBTOTAL SHEET 224				42.11		1	2							56.0	91.5																					
	SUBTOTAL SHEET 225				39.42		1	2							8.0	121.5																					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VAOT DIVISION'S "SIGN POST DESIGN GUIDELINE."

SEE SPECIAL PROVISIONS FOR ADDITIONAL SIGN INFORMATION

							FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB					
										185.5	529.0																
ROUNDING	0.41										0.5																
PROJECT TOTALS	SF 252.00	SF 0	EA. 4	EA 9			FT 0.00			FT 715.0					LB 0.00			EA. 0	LB 0.00				EA. 0	EA. 0	LB 0.00		

TRAFFIC SIGN SUMMARY SHEET 5

PROJECT NAME: CHARLOTTE
PROJECT NUMBER: F EGC 019-4(20)

FILE NAME: d78d062_frm.dgn
PROJECT LEADER: K. UPMAL
DESIGNED BY: B.KIPP
TRAFFIC SIGN SUMMARY SHEET 5

PLOT DATE: 15-MAR-2016
DRAWN BY: B.KIPP
CHECKED BY: C. LEACH
SHEET 225 OF 499