QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

R.O.W.	NON-FED. PARTIC.	EROSION CONTROL	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					164	164	LF	18'' CAAP .060	601.0215	
					164	164	LF	18'' PCCSP .064	601.0415	
					164	164	LF	18'' RCP CL III	601.0815	
					164	164	LF	18'' CPEP	601.0915	
					738	738	LF	18'' CAAP .060	601.0215	
					738	738	LF	18'' PCCSP .064	601.0415	
					738	738	LF	18'' CPEP	601.0915	
					78	78	LF	24'' CSP .064	601.0025	
					78	78	LF	24'' CPEP	601.0920	
					694	694	LF	24'' CAAP .060	601.0225	
					694	694	LF	24'' PCCSP .064	601.0425	
					694	694	LF	24'' CPEP	601.0920	
					96	96	LF	24'' CAAP .060	601.0225	
					96	96	LF	24'' PCCSP .064	601.0425	
					96	96	LF	24'' RCP CL III	601.0825	
					96	96	LF	24'' CPEP	601.0920	
					576	576	LF	24'' RCP CL III	601.0825	
					576	576	LF	24'' CPEP	601.0920	
					184	184	LF	30'' CAAP .075	601.0236	
					184	184	LF	30'' PCCSP .079	601.0436	
					184	184	LF	30'' CPEP	601.0925	
					68	68	LF	30'' RCP CL III	601.0835	
					68	68	LF	30'' CPEP	601.0925	
					86	86	LF	42'' CAAP .105	601.0252	
					86	86	LF	42'' PCCSP .109	601.0452	
					132	132	LF	48'' CAAP .105	601.0257	
					132	132	LF	48'' PCCSP .109	601.0457	
					4	4	EA	12'' CSP .064 ELBOW	601.5005	
					4	4	EA	12'' CAAP .060 ELBOW	601.5205	
					4	4	EA	12'' CPEP ELBOW	601.5802	
					4	4	EA	18'' CAAP .060 ELBOW	601.5215	
					4	4	EA	18'' PCCSP .064 ELBOW	601.5415	
					4	4	EA	18'' CPEP ELBOW	601.5814	
					5	5	EA	18'' CSPES .064	601.6015	
					5	5	EA	18'' CAAPES .060	601.6215	
					5	5	EA	18'' CPEPES	601.7015	
					1	1	EA	18'' CSPES .064	601.6015	
					1	1	EA	18'' CPEPES	601.7015	
					4	4	EA	24'' CSPES .064	601.6025	
					4	4	EA	24'' CAAPES .060	601.6225	
					4	4	EA	24'' CPEPES	601.7020	
								** END OPTION ITEMS **		
					2	2	EA	PRCCDI W/CAST IRON GRATE	604.30	-
					17	17	EA	CAST IRON GRATE W/FRAME TYPE A	604.45	-
					6	6	EA	CAST IRON GRATE W/FRAME TYPE B	604.46	-
					1	1	EA	CAST IRON GRATE W/FRAME TYPE D	604.51	-
					11500	11500	LF	6'' UNDERDRAIN	605.10	28
					700	700	LF	6'' UNDERDRAIN CARRIER PIPE	605.20	58
					32	32	EA	UNDERDRAIN FLUSHING BASIN	605.95	-
					170	170	HR	ROADWAY PATROL MAINTENANCE	607.10	EST.
					1	1	HR	BULLDOZER RENTAL, TYPE I (NOT A BID ITEM)	608.10	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

PROJECT NAME GROTON - RYEGATE
PROJECT NUMBER F 026 - 1(30)

REV. 3-31-97 dd073q2.i 1-APR-1997