QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

R.O.W.	NON-FED. PARTIC.	EROSION CONTROL	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
					1	1	LS	FIELD OFFICE - TELEPHONE (NABI)	631.25	-
			2600			2600	HR	EMPLOYEE TRAINEESHIP	634.10	EST.
					1	1	LS	MOBILIZATION	635.10	
					1	1	LS	TRAFFIC CONTROL	641.10	
					4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
					24000	24000	LF	DURABLE 4'' WHITE LINE	646.40	265
					24000	24000	LF	DURABLE 4'' YELLOW LINE	646.41	350
					75	75	LF	DURABLE 24'' STOP BAR	646.46	5
					8	8	EA	DURABLE LETTER OR SYMBOL	646.50	-
					47000	47000	LF	TEMPORARY 4'' WHITE LINE	646.60	748
					47000	47000	LF	TEMPORARY 4'' YELLOW LINE	646.61	680
					75	75	LF	TEMPORARY 24'' STOP BAR	646.66	5
					300	300	EA	LINE STRIPING TARGETS	646.73	5
					2000	2000	SY	GEOTEXTILE FOR ROADBED SUBGR. SEPARATOR	649.11	EST.
				1660		1660	SY	GEOTEXTILE UNDER STONE FILL	649.31	-
		4300				4300	SY	GEOTEXTILE FOR SILT FENCE	649.51	EST.
		1560				1560	LB	SEED	651.15	-
		250				250	LB	SEED-WINTER RYE	651.17	-
		13000				13000	LB	FERTILIZER	651.18	-
		52				52	TON	AGRICULTURAL LIMESTONE	651.20	-
		56				56	TON	HAY MULCH	651.25	-
		3300				3300	EA	HAY BALES FOR EROSION CONTROL	651.26	EST.
					2400	2400	CY	TOPSOIL	651.35	-
				300	3200	3500	SY	GRUBBING MATERIAL	651.40	-
		6150				6150	SY	EROSION MATTING	654.10	4
					10	10	EA	EVERGREEN TREES (RED PINE, PINUS RESINOSA), B&B, 10' HEIGHT	656.20	-
					2	2	EA	DECIDUOUS TREES (FLOWERING CRABAPPLE, MALUS SPP. - HARVEST GOLD CRABAPPLE), 1''- 2'' CAL, 10' HEIGHT	656.30	-
					2	2	EA	TRANSPLANTING SHRUBS	656.50	-
					130	130	SF	TRAFFIC SIGNS, TYPE A	675.20	2.805
								** BEGIN OPTION ITEMS **		
					1050	1050	LB	FLANGED CHANNEL SIGN POST	675.30	18
					1050	1050	LB	SQUARE TUBE STEEL POSTS AND ANCHORS	675.34	18
								** END OPTION ITEMS **		
					23	23	EA	REMOVING SIGNS	675.50	-
					4	4	EA	ERECTING SALVAGED SIGNS	675.60	-
	17					17	SF	TRAVEL INFORMATION SIGNS (MOD.)	680.20	.4

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

PROJECT NAME GROTON - RYEGATE
PROJECT NUMBER F 026 - 1(30)

dd073q4.i 12-MAR-1997
SHEET 9 OF 152 SHEETS