QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

DEERFIELD CHANNEL	NON-FED. PART.	GABION WALL STA.145+68 TO 147+28 RT	GABION WALL STA.148+75 TO 152+25 RT	BR 500 SERIES WALL NO.1	BR 600 SERIES WALL NO. 2	EROSION CONTROL	TRAINING	LAND-SCAPING	WETLAND MITIGAT.	BR 100 SERIES BR 24	BR 200 SERIES BR 25	BR 300 SERIES BR 25A	BR 400 SERIES BR 25B	BRIDGE NO. 26	BRIDGE NO. 27	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
																116	116	LF	42'' CAAP .105 W/6'-6'' RISER	601.0252	
																116	116	LF	42'' PCCSP .109 W/6'-6'' RISER	601.0452	
																112	112	LF	48'' CAAP .105 (2-2/3 X 1/2)	601.0257	
																112	112	LF	48'' PCCSP .109 (2-2/3 X 1/2)	601.0457	
																84	84	LF	54'' CAAP .105 (2-2/3 X 1/2)	601.0262	
																84	84	LF	54'' PCCSP .109 (3 X 1)	601.0527	
																8	8	EA	15'' CSPES .064 (2-2/3 X 1/2)	601.6010	
																8	8	EA	15'' RCPES CL III	601.6810	
																4	4	EA	18'' CAAPES .060 (2-2/3 X 1/2)	601.6215	
																4	4	EA	18'' RCPES CL III	601.6815	
																4	4	EA	18'' CSPES .064 (2-2/3 X 1/2)	601.6015	
																4	4	EA	18'' RCPES CL III	601.6815	
																1	1	EA	24'' CSPES .064	601.6025	
																1	1	EA	24'' RCPES CL III	601.6825	
																1	1	EA	30'' PCCSPES .079	601.6036	
																1	1	EA	30'' CAAPES .075	601.6236	
																3	3	EA	30'' CAAPES .075	601.6236	
																3	3	EA	30'' RCPES CL III	601.6835	
																			** END OPTION BID ITEMS **		
																2	2	EA	CONCENTRIC REDUCER SECTION	601.98	
																500	500	LF	RELAYING PIPE CULVERTS	601.99	EST.
																28	28	CY	CEMENT RUBBLE MASONRY	602.15	1.1
				416	405												821	SY	STONE MASONRY FACING (MOD.)	602.25	
																13	13	EA	PRC CURB DROP INLET W/CAST IRON GR.	604.30	
																39	39	EA	CAST IRON GRATE WITH FRAME, TYPE B	604.46	
																2	2	EA	CAST IRON GRATE, TYPE C	604.47	
																12	12	EA	CAST IRON GRATE, TYPE D	604.51	
																14800	14800	LF	6'' UNDERDRAIN	605.10	67
																1650	1650	LF	8'' UNDERDRAIN	605.11	15
																1660	1660	LF	6'' UNDERDRAIN CARRIER PIPE	605.20	22
																75	75	LF	8'' UNDERDRAIN CARRIER PIPE	605.21	4
																109	109	EA	UNDERDRAIN FLUSHING BASINS	605.95	
																8	8	EA	UNDERDRAIN FLUSHING BASINS (MOD.)	605.95	
																650	650	HR	ROADWAY PATROL MAINTENANCE	607.10	EST.
																100	100	HR	BULLDOZER RENTAL, TYPE I	608.10	EST.
																100	100	HR	BULLDOZER RENTAL, TYPE II	608.11	EST.
																100	100	HR	POWER GRADER RENTAL	608.15	EST.
																100	100	HR	ALL PURP. EXCAVATOR RENTAL, TYPE I	608.25	EST.
																100	100	HR	ALL PURP. EXCAVATOR RENTAL, TYPE II	608.26	EST.
																100	100	HR	POWER BROOM RENTAL	608.30	EST.
																100	100	HR	TRUCK RENTAL	608.37	EST.
																100	100	HR	LOADER RENTAL, TYPE I	608.40	EST.
																100	100	HR	LOADER RENTAL, TYPE II	608.41	EST.
									10							5200	5210	MGAL	DUST CONTROL WITH WATER	609.10	EST.
																20	20	TON	DUST AND ICE CONTROL W/ CALC. CHLORIDE	609.15	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DESIGN FILE NO. /78D096/DESIGN/DD096.DGN
IPARM FILE DD096Q4
PROJ. NAME SEARSBURG-WILMINGTON
PROJ. NO. NHF 010-1(18)

DRAWN BY SQDB
SQUAD LEADER DELLA SANTA
DATE PLOTTED 27-FEB-2002