

QUANTITY SHEET

**STATE OF VERMONT
AGENCY OF TRANSPORTATION**

APPROXIMATE SUMMARY OF QUANTITIES

DEERFIELD CHANNEL	NON-FED. PART TO	GABION WALL STA. 145+68 TO 147+28 RT	GABION WALL STA. 148+75 TO 152+25 RT	BR 500 SERIES WALL NO. 1	BR 600 SERIES WALL NO. 2	EROSION CONTROL	TRAINING	LAND-SCAPING	WETLAND MITIGAT.	BR 100 SERIES BR 24	BR 200 SERIES BR 25	BR 300 SERIES BR 25A	BR 400 SERIES BR 25B	BRIDGE NO. 26	BRIDGE NO. 27	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	
						200					7	13	390				1200	1200	SY	REINFORCED SOILSLOPE	612.20	
														180	305	2800	390	1000	CY	STONE FILL, TYPE I	613.10	9
																	3285	3285	CY	STONE FILL, TYPE II	613.11	6
		1500								744	3410	1415	2466				50	9585	CY	STONE FILL, TYPE IV	613.13	34
											160	160	160					480	LF	CAST-IN-PLACE CONCRETE CURB TYPE B	616.28	
																	37600	37600	CY	STONE FILL TYPE IV (MOD) (SELECTED BLASTED LEDGE)	613.13	67
																	5475	5475	LF	TREATED TIMBER CURB	616.35	21
																	8	8	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	
																	230	230	EA	YIELDING MARKER POSTS	619.17	5
																	20	20	EA	REMOVING AND RESETTING PROP. MARKER	619.20	3
																	1	1	EA	REMOVING AND RESETTING PROP. MARKER (MOD.)	619.20	
																	420	420	LF	CHAIN-LINK FENCE, 4 FEET (BLACK VINYL COATED)	620.11	
																	16	16	LF	GATE FOR CHAIN-LINK FENCE, 6 FEET	620.16	
																	3	3	EA	BRACING ASSEMBLY FOR CHAIN-LINK, 4 FEET	620.20	
																	1	1	EA	DRIVE GATE FOR WOVEN WIRE FENCE (MOD.)	620.30	
																	1600	1600	LF	REMOVING AND RESETTING FENCE	620.50	
																	2750	2750	LF	SNOW FENCE (MOD.)	620.70	25
																	14	14	LF	CEDAR LOG RAIL	621.16	
																	1350	1350	LF	CABLE GUARD RAIL	621.17	
																	16362.5	16362.5	LF	STEEL BEAM GUARD RAIL	621.20	
																	19	19	EA	MANUFACTURED TERMINAL SECTION	621.505	
																	2	2	EA	TERMINAL CONN. FOR STL. BEAM GUARD RAIL	621.53	
																	11	11	EA	ENERGY ABSORPTION ATTENUATOR	621.57	EST.
																	12	12	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
																	1	1	EA	ANCHOR FOR CABLE RAIL	621.65	
																	1	1	EA	ANCHOR FOR CABLE RAIL @ OPENINGS	621.66	
																	12	12	EA	GUARD RAIL APPROACH SECT NETC 2 RAIL	621.72	
																	2	2	EA	GUARD RAIL APPR. SECT NETC 2 RAIL (MOD.)	621.72	
																	9650	9650	LF	REMOVAL AND DISP. OF GUARD RAIL	621.80	48
																	15	15	EA	REMOVAL AND DISP. OF GUIDE POSTS	621.81	
									1									1	EA	GUIDE POSTS (MOD.)	621.85	
		720															8280	9000	LF	TEMP. TRAFFIC BARRIER (6280 - EST)	621.90	
		80															920	1000	LF	TEMP. TRAFFIC BARRIER (MOD.), (700 EST.)	621.90	
																	50	50	LF	PLASTIC WATER PIPE, RIGID	629.33	
																	3600	3600	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
																	17750	17750	HR	FLAGGERS	630.15	EST.
																	1	1	LS	FIELD OFFICE-ENGINEERS (MOD.)	631.10	
																	1	1	LS	FIELD OFFICE-SOILS & MATERIALS	631.11	
																	1	1	LS	TEST EQUIPMENT-CONCRETE	631.16	
																	1	1	LS	TEST EQUIPMENT-BITUMINOUS	631.17	
																	1	1	LU	FIELD OFFICE-TELEPHONE	631.25	
							3120											3120	HR	EMPLOYEE TRAINEESHIP	634.10	
																	1	1	LS	MOBILIZATION	635.10	
																	1	1	LS	TRAFFIC CONTROL	641.10	
																	1	1	LS	TRAFFIC CONTROL (MOD.-PUBLIC RELATIONS OFFICER)	641.10	
																	4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
																	2	2	EA	PORTABLE ARROW BOARD	641.16	
																	40900	40900	LF	4" WHITE LINE	646.20	43
																	36150	36150	LF	4" YELLOW LINE	646.21	42
																	46400	46400	LF	DURABLE 4" WHITE LINE	646.40	123
																	41600	41600	LF	DURABLE 4" YELLOW LINE	646.41	72
																	100	100	LF	DURABLE 24" STOP BAR	646.46	3
																	17	17	EA	DURABLE LETTER OR SYMBOL	646.50	
		470	1030														117500	119000	LF	TEMPORARY 4" WHITE LINE	646.60	149
		470	1030														104900	106400	LF	TEMPORARY 4" YELLOW LINE	646.61	106

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		REINFORCED SOILSLOPE
634	SY	STA. 246+75 TO 247+75 RT.
539	SY	STA. 268+00 TO 273+50 RT.
27	SY	ROUNDING
1200	SY	TOTAL

DESIGN FILE NO. /78096/DESIGN/DD096.DGN
 IPARM FILE DDO96Q5
 DRAWN BY SQDB
 SQUAD LEADER DELLA SANTA
 DATE PLOTTED 12-APR-2002
 PROJ. NAME SEARSBURG-WILMINGTON
 PROJ. NO. NHF 010-(118)
 SHEET 11 OF 435 SHEETS