STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	REFLECTIVE SIGN	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
101+50 RT. RTE.9	SPEED LIMIT 50	1	24"	30"	5						1			×																			R2-1		E-142
113+50 RT. RTE.9	BRIDGES FREEZE BEFORE ROAD	1	36"	36"	9						1			×																			VW-005		E-150
120+00 RT. RTE.9	EAST	1	24"	12"	2						1			×																			M3-2		E-136B
	VERMONT 9	1	24"	24"	4																														E-136B
151+00 LT. RTE.9	BRIDGES FREEZE BEFORE ROAD	1	36"	36"	9						1			×																			VW-005		E-150
182+00 LT. RTE.9	NATIONAL PARK ACCESS NEXT 15 MILES	1					1				1																						ERECT SALVAGED SIGN		
201+05 RT. RTE.9	WILMINGTON SEARSBURG	1	60"	7.5"	3.13						1			×																			TOWN LINE		E-124
	WINDHAM CO. BENNINGTON CO.	1	60"	7.5"	3.13																												COUNTY LINE		E-124
	0140 1416 0000	1	6"	8"	.33																												VD-700		E-138
200+05 LT. RTE.9	SPEED LIMIT 50	1	24"	30"	5						1			×																			R2-1		E-142
~~202+05~~ 200+05 RT. RTE.9	SPEED LIMIT 50	1	24"	30"	5						1			×																			R2-1		E-142
208+60 RT. RTE.9		1	30"	30"	6.25						1			×																			W2-2M		E-155
235+65 RT. RTE.9	HORSE CROSSING	1	30"	30"	6.25						1			×	INSTALL AND REMOVED AS PER JOE KELLEY. (NO LONGER NECESSARY.)																	W11-7a	NOTE: REFER TO STANDARD E-153 SIGN VW-000 SUBSITIUTE THE WORD HORSE FOR MOOSE	E-153
245+65 LT. RTE.9	HORSE CROSSING	1	30"	30"	6.25						1			×	INSTALL AND REMOVED AS PER JOE KELLEY. (NO LONGER NECESSARY.)																	W11-7a	NOTE: REFER TO STANDARD E-153 SIGN VW-000 SUBSITIUTE THE WORD HORSE FOR MOOSE	E-153
252+00 RT. RTE.9	TRAVEL INFORMATION SIGN	1						1			2			×																			ERECT SALVAGED SIGN NOT FOUND		
												FT	FT	FT 127.0	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 64.34	SF	EA.	SF				FT 127.0			FT					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

dd096.dgn

PROJECT NAME: SEARSBURG - WILMINGTON
PROJECT NUMBER: NHF 010-1(18)

FILE NAME: dd096tsl.i
PROJECT LEADER: DELLA SANTA
DESIGNED BY: SQUAD B
PLOT DATE: 30-JAN-2002
DRAWN BY: G. MEUNIER
CHECKED BY:
SHEET 89 OF 435