

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
					Roadway	ROADWAY (NON PARTI- CIPATING)	TRAINING	Erosion Control	Bridge	Full C&E	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									352		352		LF	BRIDGE RAILING, 3 RAIL ALUMINUM	525.22				
									403		403		LF	BRIDGE RAILING, ALUMINUM/PEDESTRIAN	525.23				
									1		1		LS	MAINTENANCE OF STRUCTURES AND APPROACHES	527.10				
									1		1		LS	TWO-WAY TEMPORARY BRIDGE (9240 SF - EST.)	528.11				
									1		1		EACH	REMOVAL OF STRUCTURE (11500 SF - EST.)	529.15				
									10		10		EACH	BEARING DEVICE ASSEMBLY, ELASTOMERIC PAD	531.11				
									4		4		EACH	BEARING DEVICE ASSEMBLY, POT	531.12				
														BEGIN OPTION AA					
					24						24		LF	12" CAAP .060 (2-2/3 X 1/2)	601.0205				
					24						24		LF	12" PCCSP .064 (2-2/3 X 1/2)	601.0405				
					24						24		LF	12" CPEP	601.0905				
														END OPTION AA					
														BEGIN OPTION BB					
					412						412		LF	18" CAAP .105 (2-2/3 X 1/2)	601.0217				
					412						412		LF	18" PCCSP .079 (2-2/3 X 1/2)	601.0416				
					412						412		LF	18" CPEP	601.0915				
														END OPTION BB					
														BEGIN OPTION CC					
					170						170		LF	24" CAAP .105 (2-2/3 X 1/2)	601.0227				
					170						170		LF	24" PCCSP .109 (2-2/3 X 1/2)	601.0427				
					170						170		LF	24" CPEP	601.0920				
														END OPTION CC					
					1						1		EACH	CONCRETE MANHOLE WITH CAST IRON COVER	604.11				
					9						9		EACH	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.20				
						4					4		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42				
					10						10		HR	BULLDOZER RENTAL, TYPE I	608.10				
					10						10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
					10						10		HR	LOADER RENTAL, TYPE I	608.40				
					10						10		MGAL	DUST CONTROL WITH WATER	609.10				
					1						1		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
								10			10		CY	STONE FILL, TYPE I	613.10				
									1180		1180		CY	STONE FILL, TYPE IV	613.13				
					752						752		LF	PRECAST REINFORCED CONCRETE CURB, TYPE B	616.26				
					291						291		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10				
					65						65		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11				
					18						18		SF	DETECTABLE WARNING SURFACE	618.30				
					37.5						37.5		LF	STEEL BEAM GUARDRAIL GALVANIZED	621.20				
					2						2		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
									100		100		LF	ALUMINUM APPROACH RAILING	621.74				
					27						27		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				

PROJECT NAME: **BETHEL**
PROJECT NUMBER: **BRF 022-1(14)**
FILE NAME: s78f161qty.dgn PLOT DATE: 06/16/2011
PROJECT LEADER: M. EVANS-MONGEON DRAWN BY: M. LONGSTREET
DESIGNED BY: S. SCRIBNER CHECKED BY: N. VANDENBERG
QUANTITY SHEET #2 SHEET 10 OF 148