STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REQUIRED SIGNS	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
123+75.00 RT	NORTH						X			X																							REMOVE AND SALVAGE ROUTEMARKER ASSEMBLY INSTALL IN TEMPORARY LOCATION FOR DURATION OF TEMPORARY DETOUR.		
	VERMONT 12						X			X																							REMOVE AGAIN AND RESET IN FINAL LOCATION FOLLOWING REMOVAL OF DETOUR.		
							X																												
	TO						X																												
	INTERSTATE 89						X																												
							X																												
	EAST						X																												
	VERMONT 107						X																												
							X																												
124+40.00 RT	BRIDGE 15 VT-107	1	6	8	0.33						1				8			X															VD-701		E-134
128+36.00 LT	BRIDGE 15 VT-107	1	6	8	0.33						1				8			X															VD-701		E-134
128+60.00 RT	Y	1	30	30	6.25						1					15		X															W2-5		SHSM
												FT	FT	FT	FT 16	FT 15	FT		EA	LB	LB	LB		LB	LB	LB	LB								
				TOTALS	SF 6.91	SF	EA. 9	SF				FT			FT 31					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BETHEL
PROJECT NUMBER: BRF 022-1(14)

FILE NAME: 78f161/STR/sf161traf.dgn
PROJECT LEADER: M. EVANS-MONGEON
DESIGNED BY: G.ROKES
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 20-MAY-2011
DRAWN BY: G.ROKES
CHECKED BY: S.SCRIBNER
SHEET 51 OF 148