STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REQUIRED SIGNS	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
128+75.00 LT	SPEED LIMIT 25	1	24	30	5						1					15		X	X														R2-1		SHSM
128+95.00 RT	BUSINESS SIGN						X			X																							REMOVE AND SALVAGE BUSINESS SIGN AND RESET ONCE TEMPORARY DETOUR IS REMOVED		
129+60.00 LT	STOP	1	30	30	6.25						1					15		X	X														R1-1		SHSM
129+60.00 LT	PEAVINE BLVD						X																												
129+60.00 RT	BETHEL						X			X																							REMOVE AND SALVAGE ROUTEMARKER ASSEMBLY INSTALL IN TEMPORARY LOCATION FOR DURATION OF TEMPORARY DETOUR.		
	RANDOLPH 8						X			X																							REMOVE AGAIN AND RESET IN FINAL LOCATION FOLLOWING REMOVAL OF DETOUR. PAYMENT INCIDENTAL TO ITEM 528.11.		
	NORTH						X																												
	VERMONT 12						X																												
							X																												
	TO						X																												
	US STATE 89						X																												
							X																												
					TOTALS	SF 11.25	SF	EA. 10	SF			FT	FT	FT	FT	FT 30	FT		EA	LB	LB	LB		LB	LB	LB	LB								
																FT 30				LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BETHEL
PROJECT NUMBER: BRF 022-1(14)

FILE NAME: 78F161/STR/sf161traf.dgn
PROJECT LEADER: M. EVANS-MONGEON
DESIGNED BY: G.ROKES
TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 20-MAY-2011
DRAWN BY: G.ROKES
CHECKED BY: S.SCRIBNER
SHEET 52 OF 148