



Specifications: Vermont State Highway Specifications 1926
 Rivets 3/8" unless noted
 Open Holes 1/8" unless noted
 Holes in Material 1/8" thick or less may be punched full size
 Holes in Material more than 1/8" thick shall be punched and reamed
 or drilled from the solid
 Truss members shall be assembled in the shop and holes for field
 connections reamed or filed while assembled and the members with marked
 floor beams and stringers connections to be shop-drilled and reamed
 to a metal template not less than 1/8" thick or reamed while assembled.
 Field connections for laterals, stringers and main members full size
 Shop Paint One coat of approved Red Lead and Oil

Notes:
 Rivets
 Holes
 For all Bracing unless noted

REQUIRED LIST

One	FL Beam	B1
One		B2
7		B3
2	Laterals	L1
2		L2
2		L3
2		L4
4		L5
4		L6
4		L7
4		L8
2	Holes	P1
2		P1L
16	Stringers	S1
8		S2
8	Struts	S3
8	Bolts	S4
2	Laterals	L9

BETHLEHEM STEEL COMPANY
 Bethlehem, Pa.

DETAIL OF Beams, Struts & Laterals
 STRUCTURE Bridge over White River, Bethel, New Hampshire
 CUSTOMER Chas. E. Moore, 874 1/2 rd. St. Greenfield, Mass.

SHOP PAINT
 RIVETS — OPEN HOLES — UNLESS NOTED

DRAWN BY DATE CHECKED BY DATE
 A.S. 7-16-28 J.W. 8/16/28

NO. NAME BY

Shop Bill B.S. 604 G2.
 Rev. B.S. 9

FILE: F7814 CONT. ED1447 DWG 6