



Specifications -
 Vermont State Highway Dept. 1926
 Rivets & Open Holes 13
 Holes in material 3/8 thick or less may be punched full size
 Holes in material more than 3/8 thick shall be subpunched
 and reamed or drilled from the solid.
 Truss members shall be assembled in the shop and
 holes for field connections reamed or drilled while
 assembled and the members match marked.
 Floor beams and stringer connections to be
 subpunched and reamed to a metal template not
 less than 1/8 thick, or reamed while assembled.
 Field connections for laterals, bracing and
 railing punched full size.
 Shop Paint - One coat of approved Red Lead oil

Required List

2	Top Laterals	T1
2	do	T2
3	do	T3
4	do	T4
2	Portals	PSI

BETHLEHEM STEEL COMPANY
 Bethlehem, PA.

DETAIL OF Portals - Top Laterals
 STRUCTURE Bridge over White River, Belton, New York
 CUSTOMER Charles F. Hooper - Greenfield, Mass.

SHOP PAINT See Note
 RIVETS 3/8 OPEN HOLES 13/16

DRAWN BY	DATE	DESIGNED BY	DATE	REVIEWED
FOS	7/2/28	J.H.V.	7/31/28	Hanner

REVISIONS

NO.	DATE	BY	REASON

FILE: F7814 CONT: ED1447 DWG: 7