STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 2.8	SQUARE STEEL (mm) kg/m 50 3.6	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
STA. 19+980.000, LT.	SPEED LIMIT 40		600	750	0.46 ~~0.45~~	SOFT CONVERSION (TYPE)					1					X																		R2-1		SHS
STA. 19+990.000, RT.	EAST 15 Johnson NORTH 108 Bakersfield SOUTH 108 Stowe		3810	2972		11.32					2												2				X							71	
STA. 20+020.000, LT.	WEST VERMONT 15		600 600	300 600	.19 ~~.18~~ .37 ~~.36~~						1					X																		M3-4 (GREEN ON WHITE) MI-6A		SHS E-136B
STA. 20+050.000, RT.	25 M.P.H.		900 900 450	900 900 450	.84 ~~.81~~ .84 ~~.81~~ .21 ~~.20~~						2					X																		W3-2 W2-6 WI3-1		SHS SHS SHS
STA. 20+092.250, CL			600 450	750 450	.46 ~~.45~~ .21 ~~.20~~						1					X																		R4-7 OMI-1		SHS SHS
STA. 20+107.670, RT.	YIELD		900	900	.84 ~~.81~~						1					X																		RI-2		SHS
STA. 20+108.310, LT.	WEST VERMONT 15		600 600 525	300 600 375	.19 ~~.18~~ .37 ~~.36~~ .20						1					X																		M3-4 (GREEN ON WHITE) MI-6A M6-2		SHS E-136B SHS
STA. 20+109.320, RT.	YIELD		900	900	.84 ~~.81~~						1					X																		RI-2		SHS
												m	m	m	m	m 36.6	m		EA	kg	kg	kg		kg	kg	kg	kg 198.4								
												m			m 36.6					kg			EA. 2	kg 198.4				EA.	EA.	kg					
		TOTALS			m2 6.02 ~~5.82~~	m2 11.32	EA.	m2																												

SHS = MUTCD STANDARD HIGHWAY SIGNS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: CAMBRIDGE
PROJECT NUMBER: STP 030-2(27)

FILE NAME: t78f163frm.dgn
PROJECT LEADER: JLS
DESIGNED BY: MBL
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 05-JUN-2012
DRAWN BY: MBL
CHECKED BY: JAD
SHEET 66 OF 214