STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

Metric

SUMMARY OF ESTIMATED QUANTITIES

FULL E & C	EMPLOYEE TRAINING	LANDSCAPING	TEMPORARY EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
					1050	1050	m	DURABLE 100 mm WHITE LINE	646.40	2
					1040	1040	m	DURABLE 100 mm YELLOW LINE	646.41	10
					15	15	m	DURABLE 600 mm STOP BAR	646.46	1
					13	13	EA	DURABLE LETTER OR SYMBOL	646.50	—
					300	300	m	TEMPORARY 100 mm WHITE LINE	646.60	EST
					300	300	m	TEMPORARY 100 mm YELLOW LINE	646.61	EST
					15	15	m	TEMPORARY 600 mm STOP BAR	646.66	1
					13	13	EA	TEMPORARY LETTER OR SYMBOL	646.70	—
					60	60	EA	LINE STRIPING TARGETS	646.76	—
					10	10	m^2	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	1.6
					525	525	m^2	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR	649.11	3
				35	5165	5200	m^2	GEOTEXTILE UNDER STONE FILL	649.31	6
			1860			1860	m^2	GEOTEXTILE FABRIC FOR SILT FENCE	649.51	4
			75			75	kg	SEED	651.15	4
			1			1	kg	SEED (MODIFIED) (NORTHEAST WETLAND DIVERSITY MIX)	651.15	EST
			5			5	kg	SEED, WINTER RYE	651.17	EST
			575			575	kg	FERTILIZER	651.18	7
			5			5	t	AGRICULTURAL LIMESTONE	651.20	0.4
			5			5	t	HAY MULCH	651.25	0.4
			250			250	EA	HAY BALES FOR EROSION CONTROL	651.26	EST
					410	410	M^3	TOPSOIL	651.35	2
					2000	2000	M^2	GRUBBING MATERIAL	651.40	23
			1			1	LS	EROSION & SEDIMENT CONTROL PLAN	652.10	
			250			250	HR	MONITORING EROSION & SEDIMENT CONTROL PLAN	652.20	
			1			1	LU	FIELD MAINT. OF EROSION & SEDIMENT CONTROL PLAN (NABI)	652.30	
								•••••••• DECIDUOUS SHRUBS ••••••••		
		40				40	EA	CORNUS SERICEA (RED-OSIER DOGWOOD) (60-90 CM CONT.)	656.35	—
		20				20	EA	ILEX VERTICULATA (WINTERBERRY) (60-90 CM CONT.)	656.35	—
		20				20	EA	SALIX PURPUREA (STREAMCO WILLOW) (60 CM ROOTED CUTTINGS)	656.35	—
					5	5	m^2	TRAFFIC SIGNS, TYPE A	675.20	0.14
								—— BEGIN OPTION POSTS ——		
					80	80	m	FLANGED CHANNEL SIGN POSTS	675.301	6.2
					80	80	M	SQUARE TUBE STEEL POSTS AND ANCHORS	675.341	
								—— END OPTION POSTS ——		
					20	20	EA	REMOVING SIGNS	675.50	—

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME : BERKSHIRE	PROJECT NO. : BRF-RS 0283(7)
DESIGN FILE NAME: 02837FRM.DGN	
IPARM FILE NAME: QS04.1	PLOT DATE: 18-FEB-2000
SURVEYED BY:	SURVEY DATE:
SQUAD LEADER:	DRAWN BY: C. MABY
	SHEET: 6 OF 140

78f184/zf184QS4