

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
DECK	ABUT 1	ABUT 2	APP SLAB 1	APP SLAB 2	CHANNEL	ROADWAY	EROSION CONTROL	BRIDGE	FULL E&C	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							10	20		30		CY	STONE FILL, TYPE I	613.10				
	150	380						530		530		CY	STONE FILL, TYPE III	613.12				
						3				3		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10				
						288				288		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
						1				1		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50				
						2				2		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
						4				4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED NETC 2 RAIL	621.72				
						365				365		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						230				230		LF	TEMPORARY TRAFFIC BARRIER	621.90				
						100				100		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						300				300		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
						1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
						1				1		LS	TRAFFIC CONTROL	641.10				
						1330				1330		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402				
						1330				1330		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412				
						100				100		EACH	LINE STRIPING TARGETS	646.76				
	220	560						780		780		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							180			180		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							170			170		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							20			20		LB	SEED	651.15				
							10			10		LB	SEED, WINTER RYE	651.17				
							200			200		LB	FERTILIZER	651.18				
							1			1		TON	AGRICULTURAL LIMESTONE	651.20				
							1			1		TON	HAYMULCH	651.25				
							80			80		CY	TOPSOIL	651.35				
							420			420		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN	652.10				
							30			30		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							310			310		SY	TEMPORARY EROSION MATTING	653.20				
							810			810		SY	PERMANENT EROSION MATTING	653.21				
							30			30		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
							60			60		CY	VEHICLE TRACKING PAD	653.35				
							1030			1030		LF	PROJECT DEMARCATION FENCE	653.55				
							13			13		SF	TRAFFIC SIGNS, TYPE A	675.20				
							14			14		LF	FLANGED CHANNEL SIGN POST	675.301				

PROJECT NAME: **CASTLETON**
PROJECT NUMBER: **RS 0142(10)**
FILE NAME: 78F193frm.dgn VAOT_quant.xls PLOT DATE: 02/01/2007
PROJECT MANAGER: R. WHITCOMB DRAWN BY: W. LAMMER
DESIGNED BY: W. LAMMER CHECKED BY: T. LACKEY
QUANTITY SHEET #2 SHEET 7 OF 68