STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	STANDARD	RECORDED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
400+75 RT	BRIDGE 8 VT 4A	1	6	8	0.33						1		X																					VD-701		E-134
401+57 LT	BRIDGE 8 VT 4A	1	6	8	0.33						1		X																					VD-701		E-134
401+59 RT	HILLSIDE DR	1	42	9			1				1			X		X		X																SALVAGE SIGN & REPLACE POST		E-123
402+11 RT	COMMERCIAL SIGN	1					1			2																								REMOVE & RELOCATE (ERECT) OUTSIDE OF R.O.W.		
500+27 LT	STOP	1	30	30	6.25						1			X		X		X																RI-1		E-143
500+27 LT	0041 1103 0415	1	6	10	0.42																													INSTALL ON STOP SIGN POST		E-138
500+27 RT	CRAMPTON RD	1	42	9			1				1			X		X		X																SALVAGE SIGN & REPLACE POST		E-123
500+43 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X		X																VR-017		E-141
												FT	FT ~~14~~	FT ~~32~~	FT	FT 32	FT		EA	LB	LB	LB		LB	LB	LB	LB									
											SUB TOTALS(1)	SF ~~13~~	SF	EA. 3	SF			FT ~~46~~		FT 32			LB			EA.	LB			EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: CASTLETON
PROJECT NUMBER: RS 0142(10)

FILE NAME: 78f193/str/sf193trf.dgn sf193tr3.i PLOT DATE: 09-FEB-2007
PROJECT LEADER: R. WHITCOMB DRAWN BY: T. LACKEY
DESIGNED BY: T. LACKEY CHECKED BY: C. CARLSON
TRAFFIC SIGN SUMMARY SHEET 1 SHEET 36 OF 68