

Highway Safety Corporation

Glastonbury, CT

Welding Procedure Specification

Material specification A572 gr 50, A709 Gr 50
 Welding process Gas Metal Arc Welding (GMAW)
 Manual, semi-automatic, or automatic Semi-Automatic
 Position of welding Flat (1F) or Horizontal (2F)
 Filler metal specification AWS A5.18
 Filler metal classification ER70S-3
 Electrode and manufacturer Lincoln Electric Lincoln Weld L-50
 Flux and manufacturer N/A
 Shielding gas 85% Argon / 15% CO2 Flow rate 19-27 L / min
 Single or multiple pass Single or Multiple
 Single or multiple arc Single
 Welding current DCEP
 Polarity Reverse - electrode positive
 Welding progression Stringers
 Root treatment clean base metal
 Preheat and interpass temperature base metal up to 3/4" (50°F) ; over 3/4 thru 1-1/2" (150°F) ; over 1-1/2" thru 2-1/2" (225°F)
 Postheat treatment None
 Electrode extension 3/4" ± 1/4"

WELDING PROCEDURE

Weld size	Pass no.	Electrode size	Welding parameters		Travel speed	Joint detail
			Amperes	Volts		
5/16"	1	0.062"	275 A ± 25	25 V ± 2	8-10 ipm	
7/16"	1 & 2	0.062"	↓	↓	8-10 ipm	
<p style="text-align: center;">RECEIVED</p> <p>CK'D BY <u>JEL</u> OK'D BY _____</p> <p style="text-align: center;">JUN 14 2010</p> <p>RESUBMIT _____ APPROVED <u>✓</u></p> <p>BY _____ DATE <u>6/29/10</u></p>						

This procedure may vary due to fabrication sequence, fit-up, pass size, etc. within the limitation of variables given in section 5 of latest edition AWS D1.5

WPS no. W-1757A Fabricator Highway Safety Corporation
 Revision no. 0 Prepared By: Paul Radice
 Supporting PQR no. Pre-Qualified Date 06-10-10
 Project Name East Montpelier, VT Project Number STP 037-2(9)